



NetSec · CA24154

DELIVERABLE D1 · DOCUMENTATION PACK

Website & Open Directory

Architecture, design system, and admin handover
for the COST Action NetSec website.

COST ACTION

CA24154 · Networking
European Security
Knowledge

VERSION & DATE

v1.13.2 · October 2026

AUTHOR

Dr Arthur Laudrain
MC member  · ETH Zurich



Funded by the European Union
through COST — European Cooperation
in Science and Technology.

netsec-cost.eu

The website & directory in numbers and features

A snapshot of what **netsec-cost.eu** ships today — the people it covers, the funding it points to, the technology that holds it together, and the standards it meets.

30

Participating countries — every EU/COST state with a national representative.

49

Management-Committee members listed in the open directory.

4

Working Groups, each with a chair, vice-chair, and dedicated roadmap.

5

Grant schemes documented: STSMs, Conference, Dissemination, Training, ITC.

4 yrs

ACTION DURATION

3

UI LANGUAGES

~51 %

WOMEN ON MC

€2 100

MAX GRANT

4

ITC GRANTS

€0

MONTHLY HOSTING



Apple-style glass UI

Glassmorphic cards on a dynamic aurora background, light + dark themes.



WCAG 2.1 AA

EN 301 549-aligned; zero axe-core violations on the home page.



Mobile-responsive

Every page reflows cleanly from 4K down to a 320 px phone.



Multilingual

English authoritative; French and German variants in beta with hreflang.



Auto-sync

Scheduled GitHub Actions pull bios from a Google Form and MC roster from cost.eu.



SEO-ready

Open Graph + Twitter Card + JSON-LD + sitemap + canonical URLs on every page.



GDPR-compliant

No analytics or tracking pixels; consent-gated form pipeline; full privacy notice.



Dual-licensed

Code under MIT; site copy and assets under CC BY 4.0. Reuse-friendly.

What's in this document

A self-contained reference for everyone who builds on, hands over, evaluates, or simply uses the NetSec website. Each chapter stands alone; read end-to-end for a tour, or jump in by section.

01	Overview & purpose	5
	What the site is, who it serves, and the principles behind every design choice.	
02	Architecture	11
	Tech stack, page-by-page inventory, data-flow diagrams for the weekly sync workflows, repository layout.	
03	Design system	25
	Colour tokens, typography, components, motion budget, iconography, accessibility checklist.	
04	Translation & multilingual posture	29
	How the FR/DE beta variants work, the drift-checker workflow, what falls in/out of scope.	
05	SEO & discoverability	32
	Open Graph, Twitter Card, JSON-LD, canonical URLs, hreflang, sitemap, 404 strategy.	
06	Admin guide	35
	Every account, login, and asset the site depends on; routine tasks; escalation; handover checklist.	
07	Security & DevSecOps	45
	Threat model, coordinated-disclosure policy, GitHub-native security automation, supply-chain and operational hardening.	
08	Appendix A · Accessibility standard & assessment	50
	WCAG 2.1 AA target, EN 301 549 alignment, latest self-assessment results, known limitations, reporting route.	
09	Appendix B · Licensing	53
	The dual MIT + CC BY 4.0 model and suggested attribution.	
10	Appendix C · Promotional poster	54
	An outward-facing A3 poster of the Action, ready for conferences, training schools, and noticeboards.	

Per-version summary of what this documentation pack records — kept last so the most recent revision is the final page.

How to read the diagrams

Diagrams in this document are the same Mermaid sources that live in the `docs/` folder of the GitHub repository. They render natively on github.com so anyone with read access can navigate the live versions there. The PDF embeds them as a frozen snapshot.

01 Overview & purpose

What the site is, who it serves, and the principles behind every choice.

What this site is

The NetSec website is the official front door of **COST Action CA24154 — Networking European Security Knowledge**, served at netsec-cost.eu. It is a static GitHub Pages deployment with two scheduled data-sync workflows and one third-party form processor. There is no database and no CMS. There is a build step, and it runs at deploy time rather than in the repository: see *What the deploy builds* below.

It doubles as **Deliverable D1** of the Action's Memorandum of Understanding — the open community directory that the Action committed to publishing.

Three audiences, one deliverable

Every decision in the site's design weighs three audiences against each other. A change that helps one without hurting the others is good. A change that needs to "pick a side" probably isn't ready.

The wider research community

Anyone working in or alongside European security studies. The site explains what NetSec is, who's involved, what's on the calendar, and how to engage.

Members & grant applicants

Practical resources: grant calls, the e-COST workflow, deliverables, the roadmap. The Directory and Grants page are written for them.

External evaluators & funders

COST and the European Commission, for whom the site stands as visible evidence that Deliverable D1 has been met. Privacy compliance, accessibility statement, and licensing terms are written with them in mind.

Design principles

1. **Restraint over decoration.** White space, generous line-height, and one strong colour beat busy gradients.
2. **Glass cards as the unit of UI.** Almost every distinct piece of information sits on a glassmorphic card; they define hierarchy.
3. **Stroke icons for generic glyphs, brand icons for brands.** Same concept, same icon — every conference grant gets the same microphone; every contact item gets the same envelope.

4. **Motion is a hint, not a feature.** Hover transforms ≤ 4 px, transitions ≤ 300 ms, no parallax or scroll-jacking.
5. **British English** in all user-facing copy.
6. **Accessibility first.** Every interactive element is keyboard reachable; every colour pair meets WCAG 2.1 AA; skip-links land on `#main`.

COST ACTION · EUROPEAN COOPERATION IN SCIENCE & TECHNOLOGY

Networking European Security Knowledge

An inclusive, multidisciplinary network integrating diverse perspectives on European defence and security, bridging the academia-policy divide and cultivating the next generation of security scholars.

[Security Studies](#) · [European Defence](#) · [Strategic Autonomy](#) · [Policy Impact](#)

[Discover the Action](#)
[Join the network](#)

 COST Action [CA24154](#) · running 10 Oct 2025 – 09 Oct 2029

ACTION NUMBER

CA24154

MOU

063/25

CSO APPROVAL

19 May 2025

DURATION

10 Oct 2025 – 09 Oct 2029

FIND YOUR WAY IN

Start where you are

I'm a researcher

Find collaborators across the network and see which grants are open.

[Directory](#)

[Grants](#)

I work in policy

Get the evidence base: published outputs and the terms behind them.

[Publications](#)

[Glossary](#)

I'm an Action member

Jump straight to member resources and the Wiki.

[For members](#)

[Members' Wiki](#)

I'm covering the Action

Logos, boilerplate, and the latest news in one place.

[Press kit](#)

[News](#)

UPDATES

Latest News

Announcements, calls, and milestones from the NetSec community.




Figure 1 · Home page hero, light theme. Glass nav bar, gradient title, two CTAs, "Join the network" links straight to the open Google Form.

ABOUT

About NetSec

An inclusive, multidisciplinary network bridging Europe's intellectual and analytical communities on security, across academia, policy, and practice. NetSec is COST Action CA24154, running from October 2025 to October 2029.

JUMP TO

[The Action](#)
[Leadership](#)
[Founding contributors](#)
[FAQ](#)
[Glossary](#)
[Relationship with EISS](#)

The Action

The Action fosters synergies across national and local epistemic communities, bridges the academia-policy divide, and addresses gender and generational imbalances in the field. Through interdisciplinary research, annual conferences, policy workshops, a mentorship programme, and a summer school, NetSec contributes to a cohesive European security studies community. Its work is organised across four [Working Groups](#), from building the network to fostering the next generation of scholars.

By connecting academic, policy, and practitioner communities across the continent, NetSec advances Europe's strategic autonomy in an increasingly complex global security environment.

1

Inclusive Network for Knowledge Exchange

Building a multidisciplinary community across academia, policy, and practice.

2

Translating Knowledge into Policy Impact

Closing the gap between research and decision-making on European security.

3

Developing Skills, Methods & Tools

Equipping the next generation of security scholars to address fragmentation.

IN NUMBERS

51

Management Committee members across 31 countries

142

Working Group members

84

have joined the Directory

Timeline & Deliverables



Planned



Delivered



Delivered early



M = month from start

DELIVERABLE	Year 1 2025 – 2026				Year 2 2026 – 2027				Year 3 2027 – 2028				Year 4 2028 – 2029			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
D1 First version of NetSec directory (updated regularly)		 M6		M12												
D2 First draft of manifesto					 M15											
D3																





Figure 2 · The About page (added v1.4.0). Consolidates the Action narrative previously scattered across the home page: mission, deliverables Gantt, leadership snapshot, FAQ + Glossary teasers, and the four-card Find out more discovery grid.

02 Architecture

Tech stack, pages, data flow, and repository layout.

Tech stack at a glance

The site is deliberately small. No framework, no transpiler, no bundler — just hand-authored HTML, one shared stylesheet, one shared script file, and two scheduled Python jobs that keep the data files in step with their upstream sources.



Three points to take from the diagram:

- **No back-end of our own.** Everything that looks dynamic (the directory, the grant-manager cards) is hydrated from `data/bios.json` in the visitor's browser.
- **Two sources of truth feed that file.** Member-submitted bios via a Google Form, and Action structure (WGs, leadership) via the COST website.
- **Workflow changes open a PR, never a silent push.** Every change to the directory passes through a human's review.

What the deploy builds

Until v1.14.0 the repository held every file the site serves, including the ones a script had written. That meant 582 machine-written files out of 1,193 tracked, each needing a CI check to prove it was current, and a two-line change to the stylesheet rewriting 315 pages it had not touched. Those files are now built by the Pages deploy workflow and are absent from the repository.

The deploy runs four steps in a fixed order, and the order is load-bearing:

1. `scripts/build-og-cards.py` draws the 84 per-member Open Graph cards. About 35 seconds on the runner, because Chrome starts once and the cards are screenshotted in sequence.

2. `scripts/build-profile-pages.py` writes the 252 profile pages. It runs after the cards, because a card is a page's `og:image`.
3. `scripts/build-search.sh` builds the Pagefind index.
4. `scripts/inject-seo.py --stamp-only` applies the `?v=` cache-bust tokens across the top-level pages and the 252 under `people/`. It runs last, because it stamps what the steps above wrote.

After each of the first two steps the workflow counts what was produced against the members in `data/bios.json` and refuses to publish if the two disagree. That check is not decorative: the profile pages name their card's URL without testing whether the file exists, so a silent under-render would publish 252 pages whose share image returns 404, with a green run behind it.

The drift gates that used to guard these artefacts are retired, since a gate exists to prove a committed file is current and there is no committed file. Two things stand in their place: the count assertions above, and a test asserting that the two builders agree on which members get a page and a card. A whole class of failure went with them, where a pull request touching nothing relevant went red because a generated file elsewhere was stale.

Member photographs stay committed. Their derived `.webp` variants were measured at 144 blobs and 1.9 MB across the entire history, one write per file, so moving them would have bought nothing and made Pillow a dependency of the publish path.

Site structure

Twenty-two public pages in total (each with FR and DE beta siblings, plus a locale-detecting `404.html`). One of the twenty-two, `essc-2027.html`, is parked and not yet linked from anywhere, so it does not appear in the graph below. The home page is the hub: it hosts most of the static content as anchored sections and signposts the discovery and reference pages and the members' Wiki through two dedicated home-page sections. Phase 1 of the v1.4.0 IA pass split the home page's denser blocks out into standalone pages (`about.html`, `news.html`, `roadmap.html`, `outputs.html`); v1.6.0 added the live ESSC 2026 programme page (`essc-2026.html`); v1.10.0 added the dedicated Working Groups page (`working-groups.html`); v1.12.0 added the NetSec Summer School page (`summer-school.html`), run jointly with EISS and co-located with the conference, then grew a dedicated Events page (`events.html`) gathering every NetSec event in one place. v1.13.0 added a public slide-templates gallery (`slides.html`) linked from the footer resource row on every page. v1.14.0 added the NetSec Network Map (`network-map.html`), signposted from the Directory and the Working Groups page rather than from the top nav, and a page for the Working Group 2 policy workshop in Ankara (`policy-workshop-2026.html`), reached from the home-page events block. The directory also fans out into a generated profile page per member at `people/<slug>.html` (177 pages at the time of writing, three locales each), built by `scripts/build-profile-pages.py` and counted separately from the twenty-two hand-authored pages. Three full-page applications, four reference pages branched off Home, the live conference programme, the Summer School and the Events page, and four statutory pages branch off the hub.




Figure 4 · Page graph. **Solid blue arrows** are primary navigation (the top nav links to Network, Working Groups, Grants and About from every page). **Dashed blue arrows from Home** reach the v1.4.0 IA-split pages (News, Roadmap, Outputs), the v1.6.0 ESSC 2026 programme page, the v1.12.0 Summer School and Events pages, the v1.14.0 policy-workshop page, and the four-card Find out more discovery grid at the end of the About section (FAQ, Glossary, Press kit). The Directory node also fans out into a generated profile page per member at [people/<slug>.html](#), omitted here for legibility. **The Network Map** is reached from signpost cards on the Directory and the Working Groups page rather than from the top nav, which is why two arrows converge on it. **The slide-templates gallery** sits in the footer resource row, so it is drawn grey like the statutory pages. **Dashed grey arrows** are footer-only links (Accessibility, Privacy, Licensing, Site map appear in every page's footer). **Dashed blue arrows between people and grants** are in-page cross-links between the Network and Grants pages.

Page inventory

PAGE	PURPOSE	READS AT RUNTIME
index.html	Overview, news lede, WGs, MC, events banner, <i>Find out more</i> discovery grid, <i>For NetSec members</i> Wiki signposting strip, contact. Trimmed by ~25% in v1.4.0 when the standalone About / News / Roadmap / Outputs pages took over the denser blocks.	data/events.json (events banner; added v1.6.0)
people.html	Open community directory with WG / MC / country filters; Join-the-network CTA. <i>Directory research-interest keyword filter added v1.7.0; research-theme and mentorship filters and a native mobile filter sheet added v1.11.0; a quiet "Founding contributor" badge for the founding cohort added v1.12.0.</i>	data/bios.json (all), data/keyword-aliases.json (inline fallback normaliser; added v1.7.0)
people/<slug>.html	One shareable profile page per directory member, generated by scripts/build-profile-pages.py with its own Person structured data, an ORCID-fed recent-publications list, research-theme and region chips, and "works on similar topics" facepiles that cross-link related members and mentors. Built by the Pages deploy since v1.14.0 and no longer committed. <i>Added post-conference in the v1.12.0 cycle.</i>	data/authors-index.json (Anthology slot); otherwise static, derived at build time from data/bios.json and data/orcid-works.json
grants.html	Five grant schemes, the e-COST timeline, resources, grant-manager contact cards.	data/bios.json (Grant Awarding Coordinator only)

PAGE	PURPOSE	READS AT RUNTIME
working-groups.html	The four Working Groups, each an anchored section with its MoU objective, focus areas, lead and co-lead, an expandable member grid rendered live from the COST directory, and a <i>Related events</i> block. Opens with overall stats (people, countries, groups). <i>Added v1.10.0.</i>	data/wg.json (leadership + members), data/bios.json (photos + affiliations), data/events.json (related events)
about.html	Standalone About page: mission, deliverables, <i>Find out more</i> discovery grid, milestones. <i>Added v1.4.0.</i>	—
news.html	Standalone news index, lifted out of the home page. <i>Added v1.4.0.</i>	—
roadmap.html	Public product roadmap with planned / in-progress / shipped cards; collapsible Shipped list (collapse added v1.6.0; only the most recent releases show by default). <i>Added v1.4.0.</i>	—
outputs.html	Outputs page (placeholder for COST deliverables, papers, training-school materials). <i>Added v1.4.0.</i>	—
essc-2026.html	Live ESSC 2026 programme: day chips, plenary and parallel session cards, contributions, chairs, abstracts, room badges, livestream pills, member-aware speaker popovers. <i>Added v1.6.0; speaker popover deduped onto the shared window.netsecMemberCard component v1.12.0.</i>	data/indico.json , data/bios.json (for member-aware speaker links)
summer-school.html	NetSec Early-Career Scholars Summer School (ECS ³), run jointly with EISS. Card-based page with a faculty roster whose member headshots resolve live from the directory by name, an EISS partner block with an inline logo, an application contact, and a heritage note placing it as the successor to Euro-SWAMOS. <i>Added v1.12.0.</i>	data/bios.json (faculty headshots, matched by name)
events.html	Every NetSec event in one place: upcoming and past, each card carrying dates, venue, format, and a link to its programme or registration. The conference pages settled into a fixed archive once Stockholm closed, and this page became the living index over them. <i>Added post-conference in the v1.12.0 cycle.</i>	data/events.json
faq.html	21 Q&As across six themed sections; jump-to TOC; per-question deep-link anchors. <i>Added v1.3.0; migrated from the members' Wiki.</i>	—

PAGE	PURPOSE	READS AT RUNTIME
glossary.html	~35 COST and NetSec terms across five sections; per-term deep-link anchors. <i>Added v1.3.0; migrated from the members' Wiki.</i>	—
press-kit.html	Logos with pairing rules, palette, typography, funding acknowledgements, attribution wording, do / don't rules. <i>Added v1.2.0.</i>	—
sitemap.html	User-friendly site map linking every page and every in-page anchor.	—
accessibility.html	WCAG 2.1 conformance statement.	—
privacy.html	GDPR-compliant privacy notice.	—
licensing.html	Dual-licence posture (MIT for code, CC BY 4.0 for prose) with the carve-outs spelt out. <i>Split off from privacy.html §10.</i>	—

Feature inventory

User-facing

- Light / dark theme with manual toggle and OS-pref default.
- Reveal-on-scroll powered by `IntersectionObserver`.
- Glass cards with `backdrop-filter`; graceful fallback.
- Country flags via FlagCDN for every ISO code (~200).
- Network directory: search × WG / MC chip × country, all AND-combined.
- Bio collapse: bios over 4 lines auto-add a "Show more" toggle.
- Awarding-process timeline with Before / During / After pills.
- **Site-wide Pagefind search** (added v1.4.0). Built at deploy time, separate EN / FR / DE shards, surfaced through a header overlay with keyboard shortcut.
- **The NetSec Network Map** (added v1.14.0, Beta). A force-directed canvas drawing every member, the Working Groups they sit in and the research themes they share, in three locales, with search, zoom, hub panels, a keyboard path and a build-time table of everyone it draws.
- **Live ESSC 2026 programme** at `/essc-2026.html` (added v1.6.0). Rebuilt daily from Indico via `sync-indico.py`. Day chips, parallel-session cards, livestream badges on plenaries, per-session room badges (v1.6.1), member-aware speaker popovers that resolve to a NetSec member card with photo, role, country, and bio excerpt.
- **Directory research-interest keyword pipeline** (added v1.7.0). Canonical chips on bio cards backed by `data/keyword-aliases.json`, plus a filter chip row above the grid with URL-hash persistence

Operator-facing

- **Four sync workflows** that open PRs rather than push: `sync-bios.yml` (daily, Google Form to `bios.json`), `sync-cost.yml` (weekly, cost.eu Working Group membership), `sync-indico.yml` (daily, Indico to `indico.json` with `events.json` patched in the same PR) and `roadmap-refresh.yml` (daily, the roadmap autostamp and milestone progress). The Indico and roadmap PRs auto-merge once the required checks pass. The bios and cost.eu PRs change member data, so they wait for the maintainer to merge them.
- **A failure alarm** (`failure-alarm.yml`): when a scheduled workflow or the Pages deploy fails, times out or cannot start, it opens an issue assigned to the maintainers, or comments on the open one for that workflow.
- `data-bios-roles` attribute pattern: any element with it gets hydrated from `bios.json` at load.
- MC-member auto-tagging via `mc-members.json`.
- Brand-accurate social icons (Simple Icons SVGs).
- Stable slug-based member IDs for deep-linking.
- **Release script extensions** in `scripts/release.sh` (v1.7.0): `promote-roadmap.py` flips public roadmap cards from planned to shipped on `/roadmap.html` in EN, FR and DE during release; a PDF-cover-bump reminder prints on minor and major releases; open issues tagged with the milestone being cut are listed before the script exits.
- CSS class-collision lint via `scripts/check-css-class-`

(`#keywords=slug-one,slug-two`) and OR semantics across selected chips. Top-8 chips shown by count.

- **iCalendar feed** at `/calendar.ics` (added v1.4.0). The events block carries a `webcal://` Subscribe button. The feed is regenerated whenever `events.json` changes (v1.6.1).
- **Weekly member spotlight** (added v1.11.0). A home-page block features one network member each week, drawn from the directory. This is an **inclusiveness measure for early-career investigators**: the rotation weights ECIs and Inclusiveness Target Country members upward and de-prioritises full professors (inferred from the public job title), so the visibility goes to the people who benefit from it most. Gender is not part of the score and is corrected by hand. The block is dormant until at least ten members have both a photo and a written bio.

`collisions.py` (added v1.6.0).

- Photo-source SHA-256 caching in `sync-bios.py` (added v1.5.0) so unchanged upstream photos do not get re-encoded and dirty the working tree.
- **Spotlight rotation** (`spotlight-rotate.yml` + `rotate-spotlight.py` , added v1.11.0): a weekly balanced-rotation score over `bios.json` (early-career and ITC boosts, Working-Group balance, recency hold-out) picks the featured member and opens an auto-PR. A `pinned` field in `data/spotlight.json` is the manual override and the way to correct any imbalance, since gender is deliberately not scored.

Data flow — how a bio gets onto the site

The end-to-end path for a new member submission, from filling in the form to the live directory.




Figure 5 · Bios pipeline. Required consent on the form is what gates what reaches the Sheet. Photos are downscaled with Pillow before commit.

Data flow — how a cost.eu change propagates




Figure 6 · cost.eu pipeline. The Leadership table on cost.eu has a malformed closing tag that breaks BeautifulSoup, so the script falls back to regex over the raw HTML.

Data flow — contact form




Figure 7 · Contact submissions never touch our repo. Formspree is the only third party that sees them, acting as data processor under Standard Contractual Clauses.

Data flow: Indico to live programme

The path from a daily change inside the Indico instance to the rendered programme on `/essc-2026.html`. The events-block banner on the home page is patched in the same run so the public surface does not drift from the live programme.




Figure 8 · ESSC pipeline. The Indico-to-events.json patch step closes the drift gap between the live programme and the home-page banner. Added v1.6.0; patch step added v1.6.1; PR-based flow (no direct push) added in v1.6.1 for branch-protection compatibility.

Data flow: roadmap autostamp

Once a day, the autostamped block in `docs/roadmap-2026.md` is rewritten from the changelog's `[Unreleased]` section, and `data/roadmap-progress.json` is refreshed from the GitHub milestones. The workflow runs on a schedule and not on every changelog change, which once produced 36 automated PRs in a day. `scripts/release.sh` refreshes both itself, so a release never waits on the schedule.




Figure 9 · Roadmap autostamp. Added v1.7.0, made a daily refresh in v1.14.0. The scripts never edit `CHANGELOG.md` or the planned / in-progress / shipped cards on the public roadmap.html directly. They refresh only the markdown autostamp block read by Action evaluators and the milestone progress file.

Data flow: news to social media

News on the site (and the weekly member spotlight) can be reposted to Bluesky and LinkedIn, with a human approval step before anything goes public. The pipeline is a *consumer* of surfaces that are already published, so it never invents content: it reposts the RSS feed and the rotated spotlight. Two posting paths run side by side, with different risk profiles.

The **news / curated-thread path** is approval-gated: a job pauses inside the `social` environment until a required reviewer reads the exact post and approves it. A news item can opt out, or hand itself to a hand-written multi-post thread, through a `social` field in `data/news.json`. The **weekly spotlight path** is treated as low-risk and posts ungated from the rotation workflow inside a separate `social-auto` environment. Both paths share one dedup ledger (`data/social-posted.json`), so nothing is ever posted twice.




Figure 10 · Social pipeline. Added v1.12.0. The `social` gate protects both the action (posting) and the access: the Bluesky and LinkedIn credentials are environment secrets, released only after a reviewer approves. The dedup key is the news item id (its `<guid>`), not the link, so two items pointing at the same page never collide.

Data flow: per-member share cards

Every directory member has a personal Open Graph image at `assets/og/people/<slug>.png`, so sharing their profile unfurls as *that person* rather than the generic site card. These are never hand-drawn: member data flows in from the daily bios sync, and `scripts/build-og-cards.py` draws the cards during the Pages deploy. They are not committed.

A card is keyed by a hash of exactly the fields it shows (name, role, affiliation, country and flag, headshot path plus the photo's SHA-256, working-group pills, mentorship, STSM hosting). The builder re-renders only the members whose hash changed or whose PNG is missing, recorded in `_manifest.json`, so the weekly auto-PR stays churn-free instead of rewriting dozens of binaries. Editing research keywords alone does not re-render a card, because keywords are not on it.




Figure 11 · Per-member OG cards. Added v1.12.0. Cards render over the Chrome DevTools Protocol with an exact 1200×630 clip, not the `--screenshot` CLI flag, which on macOS subtracts the window chrome and clips the footer. A `--check` gate in CI fails any PR whose data changed without its card, so a card can never drift behind the data.

The ESSC live programme in practice



Figure 12 · The European Security Studies Conference 2026 live programme (added v1.6.0, refined through v1.6.1). Day chips at the top; parallel session cards with room badges, livestream pulses on plenaries, and inline-expand abstracts on contributions. Speaker names that resolve to a NetSec member open a glass preview popover on hover. Cropped from the top of the live page; the full programme spans several screen-heights and is best read at netsec-cost.eu/essc-2026.html.

The Directory in practice




Figure 13 · The Directory. Four filter axes (free-text search, WG / MC chip, country, research-interest chip row) AND together so they can be stacked. The research-interest filter row above the grid (added v1.7.0) shows the top eight canonical keywords by submission count; clicking a chip narrows the directory and persists the selection in the URL hash for sharing. Cropped from the top of the live page to show the filter chrome above the grid; the full member list continues below.

The Network Map




Figure 14 · The NetSec Network Map (v1.14.0, Beta). Each member is a dot, pulled towards the Working Groups they sit in or, under the second lens, the research themes they work on. The statistics strip says how many of the 192 people the current lens can actually draw, since a member on no roster has nothing to be drawn towards. People sitting between two hubs are the bridges of the network. Two overlays add who shared a conference panel and who is offering or seeking mentorship. Search finds a person and spotlights their connections, and the whole map is reachable from the keyboard, with a table of everyone it draws written into the page below the canvas. Cropped from the top of the live page.

Repository layout

```
.
├── index.html                # Home
├── about.html               # About (v1.4.0)
├── news.html               # News index (v1.4.0)
├── roadmap.html            # Public roadmap (v1.4.0)
├── outputs.html            # Outputs placeholder (v1.4.0)
├── essc-2026.html          # ESSC 2026 live programme (v1.6.0)
├── working-groups.html     # The four Working Groups (v1.10.0)
├── summer-school.html      # Summer School ECS3 (v1.12.0)
├── events.html             # Events index (v1.12.0)
├── people.html             # The Directory
├── people/<slug>.html       # Generated per-member profile pages (v1.12.0)
├── grants.html             # Grants & Calls
├── faq.html                # Public FAQ
├── glossary.html           # COST + NetSec terminology
├── press-kit.html          # Logos, palette, funding acknowledgements
├── accessibility.html      # WCAG statement
├── privacy.html            # GDPR notice
├── licensing.html          # Dual-licence posture
├── sitemap.html            # User-friendly site map
├── 404.html                # Locale-detecting not-found page
├── *.fr.html *.de.html     # French + German beta of every page above
├──
├── sitemap.xml             # Machine-readable sitemap, hreflang siblings
├── calendar.ics            # iCalendar feed (v1.4.0); regenerated on events.json change
├── CNAME                   # GitHub Pages → netsec-cost.eu
├──
├── assets/
│   ├── css/site.css        # Single shared stylesheet
│   ├── js/site.js          # Nav, theme, reveal, tour, netsecT()
│   ├── js/people-directory.js # Shared directory renderer, one module for all three locales
│   └── images/people/*.{jpg,png} # Member headshots
├──
├── data/
│   ├── bios.json           # The directory
│   ├── mc-members.json     # MC roster per country
│   ├── events.json         # Home-page event banner schema (v1.6.0); carries indicoEvent
│   ├── indico.json         # Synced ESSC 2026 programme (v1.6.0)
│   ├── wg.json             # Per-WG leadership + members from cost.eu (v1.10.0)
│   ├── roadmap-progress.json # GitHub milestone progress for the roadmap (v1.10.0)
│   ├── keyword-aliases.json # Curated acronyms + alias map for directory keywords (v1.7.0)
│   ├── orcid-works.json     # ORCID publications cache feeding cards + profile pages (v1.7.0)
│   └── i18n-state.json      # SHA-1 stamps for drift checker
├──
├── scripts/
│   ├── sync-cost.py         # cost.eu → WG_MAP + roles + data/wg.json
│   ├── sync-bios.py         # Google Form → bios.json (photo SHA-256 cache v1.5.0;
│   │                       # canonical_keywords + keyword_aggregate v1.7.0)
│   ├── sync-indico.py       # Indico → indico.json + events.json + calendar.ics (v1.6.0)
│   ├── sync-roadmap.py      # CHANGELOG → docs/roadmap-2026.md autostamp (v1.7.0)
│   ├── sync-roadmap-progress.py # GitHub milestones → data/roadmap-progress.json
│   ├── promote-roadmap.py   # Flips public roadmap cards planned→shipped on release (v1.7.0)
│   ├── test-sync-bios.py    # Pipeline tests
│   └── test-sync-indico.py  # Pipeline tests
```

```

└─ inject-seo.py           # Canonical + OG + JSON-LD generator
└─ build-profile-pages.py  # Renders people/<slug>.html from bios + ORCID works (v1.12.0)
└─ check-i18n-drift.py    # Reports stale translations
└─ check-css-class-collisions.py # Lints accidental class-name reuse (v1.6.0)
└─ check-ally.sh          # axe-core scan wrapper
└─ check-links.sh         # Internal-link checker
└─ release.sh             # Cuts a tagged release; calls promote-roadmap on release day
└─ bios-source.json       # Pipeline config
└─ requirements.txt

└─ .github/workflows/
  └─ pages-deploy.yml      # Builds generated files, deploys to Pages (push + every 6 h)
  └─ sync-bios.yml         # Daily cron, opens PR, merged by hand
  └─ sync-cost.yml         # Weekly cron, opens PR, merged by hand
  └─ sync-indico.yml       # Daily cron, opens PR + auto-merges (v1.6.0; PR-based v1.6.1)
  └─ roadmap-refresh.yml   # Daily autostamp + milestone progress (v1.14.0)
  └─ spotlight-rotate.yml  # Weekly member spotlight + social post
  └─ social-bluesky.yml    # Approval-gated news posts to Bluesky + LinkedIn
  └─ failure-alarm.yml     # Files an assigned issue when a scheduled run fails
  └─ launch-ga-link-check.yml # Link check on HTML PRs + weekly
  └─ i18n-drift.yml        # Runs drift checker on HTML PRs
  └─ ...                   # 20 further lints, gates and housekeeping jobs

└─ docs/                  # Internal documentation
  └─ architecture.md      design-system.md  admin-guide.md
  └─ i18n.md              seo.md            bios-setup.md
  └─ roadmap-2026.md       # AUTOSTAMP block written by roadmap-refresh.yml
  └─ pdf/                  # Source for this documentation pack
  └─ promo/                # Promotional poster (A3) + card-size

└─ CHANGELOG.md           # Keep a Changelog, SemVer 2.0.0; hybrid lede + themes + index format (v1.5.0)
└─ LICENSE                # MIT (code)
└─ LICENSE-CONTENT        # CC BY 4.0 (prose)
└─ README.md
└─ SECURITY.md

```

Conventions worth knowing

- **British English** in user-facing copy.
- **Slugs** are produced by an identical `slugify()` in both Python scripts (strip salutation, drop diacritics, drop apostrophes, lowercase, hyphenate). Both scripts must agree or member IDs drift.
- **Member IDs** are the slug of the cleaned name — stable across re-submissions, used as `id` on member cards so `/people.html#arthur-laudrain` resolves.
- **Comments in CSS / JS / Python** are full sentences explaining *why* the code is there, not paraphrasing *what* it does.
- **No JS framework, no transpiler, no bundler.** Anything more than that needs an issue first.

03 Design system

Tokens, components, motion, and the accessibility floor.

The site follows an **Apple-inspired glassmorphism** language layered onto EU and COST brand colours. It should feel modern, trustworthy, and Brussels-adjacent without ever feeling corporate.


Colour tokens

Defined in `assets/css/site.css` on `:root` (light) and `:root.dark` (dark). Always reference the token, never the raw hex.

TOKEN	LIGHT VALUE	USED FOR
<code>--bg-0</code>	<code>#f6f8fc</code>	Page background
<code>--bg-1</code>	<code>#eef2fb</code>	Slight elevation backdrop
<code>--ink</code>	<code>#0b1220</code>	Headings, primary copy
<code>--ink-2</code>	<code>#2b3850</code>	Body copy, sub-headings
<code>--muted</code>	<code>#5a6679</code>	Captions, meta, fineprint
<code>--line</code>	<code>rgba(11,18,32,.08)</code>	Dividers, low-emphasis borders
<code>--glass-bg</code>	<code>rgba(255,255,255,.55)</code>	Default glass card fill
<code>--glass-bg-strong</code>	<code>rgba(255,255,255,.72)</code>	Sticky nav, opaque cards
<code>--accent</code>	<code>#003399</code> EU blue	Primary buttons, focus rings, accents
<code>--accent-2</code>	<code>#0a84ff</code> Apple blue	Hyperlinks, secondary accent
<code>--accent-glow</code>	<code>rgba(10,132,255,.35)</code>	Soft glow under hovered buttons
<code>--ease</code>	<code>cubic-bezier(.22,.61,.36,1)</code>	Default transition curve

Dark theme inverts `--bg-*`, `--ink*`, `--line`, and `--glass-*` but keeps `--accent` and `--accent-2` identical so brand colour is constant across modes.

Typography



Both faces load once from Google Fonts via a `<link rel="preconnect">` + stylesheet pair in every page's `<head>`. Heading hierarchy across the site:

LEVEL	COUNT	EXAMPLE
<code>h1</code>	1 per page	"The Directory", "Grants & Calls"
<code>h2</code>	6–9	Major sections
<code>h3</code>	~20	Sub-sections, member names
<code>h4</code>	~18	Card titles, country names

Never skip a level (no `h2` → `h4`).

Component kit

Every distinct visual element belongs to a small, named set of CSS classes. Reuse the existing ones; don't introduce parallels.

`.glass`

The workhorse card — semi-transparent fill, blurred backdrop, soft shadow, hover lift. Used for news cards, member cards, country cards, grant cards, the search toolbar, and more.

`.btn` / `.btn-primary` / `.btn-ghost`

Primary fills with `--ink`, hover shifts to `--accent`. Ghost is transparent with a border and a slight hover lift.

`.chip` / `.wg-chip`

Pill-shaped labels. Working-Group chips are colour-coded 1–4 so a viewer can scan a member card and place them by colour alone.

`.timeline`

Vertical timeline on the Grants page — gradient rail with numbered nodes, Before / During / After phase pills, dashed-circle divider at the activity boundary.

`.mc-stats`

Three-up snapshot on the home page (49 reps, 30 countries, ~51 % women). Stacks to one column on phones.

`.members-toolbar`

Toolbar at the top of the Directory page. Free-text search + WG / MC chip + country dropdown — all AND-combined by the directory's render loop.

Iconography

Two SVG styles coexist by design:

STYLE	WHEN TO USE	SOURCE
Stroke	Generic glyphs (envelope, globe, briefcase, microphone)	Lucide-style: <code>stroke="currentColor"</code> , <code>stroke-width="1.9"</code> , <code>fill="none"</code>
Filled brand	Recognisable brand marks (ORCID, LinkedIn, X, Bluesky, Mastodon)	Simple Icons SVG paths; <code>fill="currentColor"</code> (ORCID in brand green via <code>.contact-orcid</code>)

Same-concept-same-icon rule: every conference grant uses the same microphone icon; every contact-item uses the same envelope. Consistency lets users build muscle memory for what an icon means.

Motion

- `.reveal` — fades in + slides up 12 px when intersecting the viewport. Default state is *visible*; the fade only engages once JS has confirmed the observer fires. If JS fails for any reason, content stays visible — never invisible.
- `.blob` — three large translucent radial blobs in `.ambience`, drifting on a 22–34 s loop. Pure decoration; `aria-hidden="true"`.
- **Glass-card hovers** — 250 ms `translateY(-4px)` + shadow swap.
- **Theme toggle** — instant; the FOUC-prevention script runs before paint.

Accessibility checklist for new work

- All interactive controls reachable with keyboard alone.
- Visible focus ring (use the existing `:focus-visible` style).
- `aria-label` on icon-only buttons; `title` for hover hints.
- Heading levels follow the hierarchy table above — no skipping.
- Colour contrast meets WCAG 2.1 AA in **both** themes.
- No content hidden behind `:hover` alone.
- Animations respect `prefers-reduced-motion`.
- Skip-link still focuses `#top` (home) or `#main` (other pages).

04 Translation & multilingual posture

How the FR/DE beta works; how it stays in step with the English source.

The NetSec site ships in three languages: **English** (authoritative), **French** (beta), and **German** (beta). Every public page has a sibling at `page.fr.html` and `page.de.html`, surfaced through a language switcher in the header.

Budget posture

The Action has **no recurring translation budget** and no plan for a paid translation API. Translations are authored by hand, once, and refreshed only when English drifts meaningfully. The site never makes a translation API call at build or runtime.

How a language switch happens

The switcher in the header is implemented as three sibling `<a>` links — *not* a JS routing trick. Clicking *FR* on `/people.html` navigates to `/people.fr.html`. The page that gets served is the page the visitor lands on; there is no rewrite layer.

Three pieces of state cooperate:

1. `<html lang="...">` on every variant — drives `:lang()` selectors and assistive-tech voice.
2. `localStorage.netsec-lang` — the visitor's saved preference. On any home-page hit (`/` , `/index.fr.html` , `/index.de.html`), `assets/js/site.js` reads this and silently redirects to the saved variant if it differs from the URL.
3. `<link rel="alternate" hreflang="...">` blocks in every page's `<head>` — tell search engines which URLs are language variants of each other (and which is `x-default`).

What's translated, what isn't


CONTENT TYPE	TRANSLATED?	WHY
Page chrome — nav, footers, headings, form labels, captions	Yes	Hand-authored in each <code>.fr.html</code> / <code>.de.html</code> file.
JS-rendered strings (search placeholder, "No results", toast confirmations)	Yes	Loaded via <code>window.netsecT()</code> from a per-locale catalog in <code>assets/js/site.js</code> .
Member-submitted bios in <code>data/bios.json</code>	No	Members write their own bio in whichever language they choose; we don't paraphrase someone else's self-description.

CONTENT TYPE	TRANSLATED?	WHY
Calls of grants, dates, place names	No (kept in source language)	Calls are authoritative documents; translating them risks introducing error.
COST / EU boilerplate (funding statement, emblem alt-text)	Yes	Translations exist in COST's official toolkit; we reuse those.

Components added in v1.4.0, v1.6.0 and v1.7.0 follow the same posture: **Pagefind search** (the search overlay's placeholder, no-results message, keyboard-shortcut hint), the **ESSC programme renderer** (day-chip labels, session-card chrome, livestream and room-badge text), and the **directory keyword filter** (chip-row heading, clear-filters button, the "X of Y members" counter) all route their runtime label strings through `window.netsecT()`, the in-browser translation helper defined in `assets/js/site.js`. Member-submitted content (bios, Indico contribution abstracts, keyword text) remains unmodified in whatever language it was authored in; only the surrounding chrome is translated.

Keeping translations in step: the drift checker

Hand-translated sibling files drift out of sync whenever English changes and the translator forgets to update FR/DE. To make that visible, we maintain a small manifest at `data/i18n-state.json` that stamps a SHA-1 of each English source page at the moment its translations were last refreshed.



Run locally:

```
python3 scripts/check-i18n-drift.py          # report which pages have drifted
python3 scripts/check-i18n-drift.py --stamp en # refresh EN sha after editing English
python3 scripts/check-i18n-drift.py --stamp fr # mark FR refreshed for changed pages
```

Refreshing a translation

1. Edit the English source (e.g. `people.html`).
2. Run the drift checker — note which pages it flags.

3. Translate the same change into `people.fr.html` and `people.de.html` by hand. Keep tag names, IDs, class names, and href targets identical; only translate text content and certain visible attributes (`title`, `aria-label`, `alt`).
4. Re-run the drift checker with `--stamp en --stamp fr --stamp de` to refresh all three.
5. Commit alongside the English change so the manifest stays meaningful.

What we deliberately don't do

- **No machine translation at build or runtime.** Quality is too uneven for an official COST deliverable, and we have no budget for an API.
- **No URL-based locale negotiation** (e.g. `/fr/people`). The static sibling-files approach keeps GitHub Pages routing simple, lets us version each translation independently, and removes any need for server-side logic.
- **No language gateway page.** The visitor lands on whichever URL they typed; client-side JS may redirect them to a saved preference, but only on the home page.

05 SEO & discoverability

Crawl directives, social-share cards, and how it all stays in sync.

The site implements the industry-standard SEO checklist for a multilingual static site: machine-readable sitemap, canonical URLs, hreflang annotations, Open Graph + Twitter Card metadata, JSON-LD structured data, and a designed 404 page. None of it is hand-typed twice — a single Python script regenerates the per-page metadata block from a small source-of-truth.


What's in place

LAYER	WHERE	WHAT IT DOES
Crawl directives	<code>robots.txt</code> at site root	<code>Allow: /</code> ; points crawlers at <code>sitemap.xml</code> . No private paths to disallow.
Discovery	<code>sitemap.xml</code> at site root	Every public page with <code><lastmod></code> , <code><changefreq></code> , <code><priority></code> , and <code>xhtml:link</code> hreflang annotations for FR/DE/x-default.
Canonical URLs	<code><link rel="canonical"></code> on every page	Points at the page's own URL — keeps the <code>.fr.html</code> / <code>.de.html</code> variants from looking like duplicates.
Language alternates	<code><link rel="alternate" hreflang></code> blocks	Matches the sitemap; explicitly declares <code>x-default</code> → English.
Open Graph	<code>og:title</code> / <code>og:description</code> / <code>og:url</code> / <code>og:type</code> / <code>og:image</code> / <code>og:site_name</code> / <code>og:locale</code>	One block per page, locale-aware.
Twitter Card	<code>summary_large_image</code>	Title / description / image mirror the OG values.
JSON-LD	<code><script type="application/ld+json"></code> per page	<code>Organization</code> schema on every page; <code>WebSite</code> on <code>/</code> ; per-page <code>WebPage</code> .
Social-share image	<code>assets/images/og-image.png</code>	1200 × 630 branded card used by Facebook, Twitter/X, LinkedIn, WhatsApp, Slack, Discord, iMessage.
Theme colour	<code><meta name="theme-color" content="#003399"></code>	Mobile browser chrome adopts the EU blue.

LAYER	WHERE	WHAT IT DOES
404 page	<code>404.html</code> at site root	Served by GitHub Pages on any unknown URL. Auto-detects browser language and points the visitor back at the right localised home. Carries <code>noindex</code> .

How it stays in sync — `inject-seo.py`

The OG / Twitter / canonical / JSON-LD blocks are **generated**, not hand-typed. The generator lives at `scripts/inject-seo.py` and is idempotent: it looks for sentinel comments (`<!-- seo:auto BEGIN -->`) and `<!-- seo:jsonld BEGIN -->`) and rewrites the block in place, or inserts a fresh one between the hreflang block and `<link rel="icon">`.



Use:

```
python3 scripts/inject-seo.py          # rewrites the SEO block in every HTML file
python3 scripts/inject-seo.py --check  # report-only mode (non-zero exit on drift)
```

Adding a new page

1. Hand-author a unique `<title>` (≤ 60 chars) and `<meta name="description">` (≤ 160 chars).
2. Add the `<link rel="alternate" hreflang>` block in `<head>` for EN/FR/DE/x-default.
3. Set `<html lang="...">` correctly.
4. Add the page to the `PAGES` list at the top of `scripts/inject-seo.py`, then run the script.
5. Add a `<url>` entry to `sitemap.xml`.
6. Add the page to `data/i18n-state.json` and stamp the EN SHA.
7. Run the drift checker to confirm everything is fresh.

What's deliberately *not* implemented

THING	WHY
Google Analytics / Tag Manager	Privacy posture — no third-party trackers (see privacy.html).
<code><meta name="keywords"></code>	Ignored by all major search engines for ~15 years.
AMP / amp-html	Performance budget is already very low; AMP would add complexity without measurable gain.
<code>rel="prev"</code> / <code>rel="next"</code> pagination	No paginated content on the site.
hreflang on sub-page anchors	hreflang applies to URLs, not anchors. Deep-links into a translated page inherit the page's lang.

Verifying on the live site

- **Open Graph debugger:** paste any URL into [opengraph.xyz](#) or LinkedIn's Post Inspector.
- **JSON-LD validator:** paste the URL into [Google's Rich Results test](#). The Organization / WebSite / WebPage nodes should all validate.
- **Lighthouse SEO audit:** any Chromium DevTools → Lighthouse. Target score ≥ 95 .

Known limits — what GitHub Pages can't do

- **No HTTP response headers.** So `Content-Language` , `Vary: Accept-Language` , and similar headers are unavailable. The `<html lang>` attribute is the next-best signal and is in place.
- **No server-side content negotiation.** Auto-redirect based on `Accept-Language` only works after the page loads. We do the redirect client-side via the saved `netsec-lang` preference, so the very first hit always lands on whatever URL the visitor typed.

06 Admin guide

Accounts, routine tasks, escalation, and handover.

This section answers: "It's six months later, the maintainer is on parental leave, something needs editing — where do I start?"

Accounts & assets — domain and hosting

ASSET	LOCATION	OWNER / LOGIN
<code>netsec-cost.eu</code>	Namecheap	Registered under Dr Moritz Weiss (Action Chair); admin contact Dr Arthur Laudrain
GitHub Pages routing	Repo Settings → Pages	GitHub org <code>EISSeuropa</code>
TLS certificate	Auto-managed by GitHub Pages	n/a (Let's Encrypt)

Accounts & assets — code and pipelines

ASSET	LOGIN	NOTES
GitHub repository <code>EISSeuropa/netsec.github.io</code>	GitHub account in the <code>EISSeuropa</code> org	Action Chair, Vice-Chair, maintainer.
Google Form "Join the NetSec network"	Google account that owns the form	URL stored in <code>scripts/bios-source.json</code> → <code>form_url</code> .
Linked Google Sheet	Same Google account	Publish-to-web enabled (CSV). Required-consent step on the form gates what reaches it.
Published CSV URL	n/a (public capability)	Stored in <code>scripts/bios-source.json</code> → <code>csv_url</code> . Anyone with the URL can read the Sheet — the form's required-consent step is what gates the content.
Formspree project (id <code>meenwyrb</code>)	Formspree account	Free tier; submission destination is the Action mailbox.

Bus-factor reminder

Every admin task below assumes **at least two people** hold `EISSeuropa` org membership with *Maintain* permission on the repository. If that drops to one, escalate.

Accounts & assets — branding

ASSET	LOCATION	LICENCE
COST logo	<code>assets/images/cost-logo.jpg</code>	© COST Association — used per COST visual-identity guidance.
EU emblem	Inlined SVG in every footer	Used per the EU visual-identity manual for <i>Funded by the EU</i> communication.
NetSec wordmark	Pure CSS letter-mark — no asset	© COST Action NetSec.
Member headshots	<code>assets/images/people/<slug>.*</code>	© the individual, displayed with consent.
Country flags	FlagCDN (loaded at runtime)	Flags themselves public domain; CDN MIT.

Reviewing a sync PR

Four sync workflows open pull requests against `main` on dedicated automation branches. The bios and cost.eu PRs wait for the maintainer to merge them, and the Indico and roadmap PRs auto-merge once the required checks pass. A run with nothing to change opens no PR.

WORKFLOW	CADENCE	BRANCH	WHAT THE DIFF COVERS
<code>sync-bios.yml</code>	Daily (05:15 UTC)	<code>bios-sync/auto</code>	New or edited bios in <code>data/bios.json</code> plus any photo updates under <code>assets/images/people/</code> . Reviewer attention focuses here, since every new bio passes through a human's eyes.
<code>sync-indico.yml</code>	Daily	<code>indico-sync/auto</code>	Refresh of <code>data/indico.json</code> from the Indico instance; when <code>events.json</code> carries a matching <code>indicoEventId</code> , the home-page banner summary / start / end and <code>calendar.ics</code> are patched in the same PR. Skim the diff for sensible session titles, room names, and speaker spellings.
<code>sync-cost.yml</code>	Weekly (Mondays 05:00 UTC)	<code>cost-sync/auto</code>	Working Group membership, leadership and the MC roster from cost.eu, in <code>data/wg.json</code> , <code>data/mc-members.json</code> and <code>data/bios.json</code> . The PR body leads with a one-line change summary.

WORKFLOW	CADENCE	BRANCH	WHAT THE DIFF COVERS
<code>roadmap-refresh.yml</code>	Daily (07:00 UTC)	<code>roadmap-refresh/auto</code>	The AUTOSTAMP block in <code>docs/roadmap-2026.md</code> (bullet counts per category in <code>[Unreleased]</code> plus the latest SemVer tag) and <code>data/roadmap-progress.json</code> from the GitHub milestones.




Figure 16 · Soft-review policy. A PR that changes member data waits for the maintainer's merge. The Indico and roadmap PRs merge themselves on green checks, and anything wrong is fixed at its source.

The reviewer's job is **not** to fact-check research claims; it is to catch:

- Obvious typos in bios (ALL-CAPS surnames, missing capitals).
- Broken or mis-targeted links (ORCID under the LinkedIn field).
- Photos that aren't headshots.
- Anyone who didn't tick consent (sync drops these automatically, but worth a glance).
- On Indico PRs: garbled session titles or speaker names; missing rooms on parallel sessions.
- On roadmap-autostamp PRs: a category count that doesn't match what you remember merging.

Other routine tasks

Manually triggering a sync

1. Go to *Actions* in the GitHub repo.

2. Pick the workflow you need: *Sync member bios from Google Form*, *Sync WG membership from cost.eu*, *Sync events from Indico*, or *Refresh roadmap surfaces*.
3. Click **Run workflow** → **main** → **Run**.
4. Watch the run. A bios or cost.eu PR then waits for you to merge it, and an Indico or roadmap PR merges itself once the required checks pass.

Removing a member at their request

1. Delete the relevant `members[]` entry from `data/bios.json`.
2. Delete the headshot at `assets/images/people/<slug>.jpg` if present.
3. Open the Google Sheet and either delete the row, or clear the consent column (next sync drops them anyway).
4. Commit with message `bios: remove <slug> on request`.

Form-side caveats (directory management)

The Google Form is the primary submission surface for bios. Two caveats worth knowing:

- **Photo replacements need a workaround (#183).** A member who wants to replace their photo cannot edit their submitted response (a Google Forms limitation when the file-upload question is involved). The agreed workaround is for the admin to swap `assets/images/people/<slug>.jpg` directly and either drop the corresponding photo-source SHA-256 entry or update it to match the new file, so that `sync-bios.py` does not overwrite the new image on the next run.
- **Form settings:** "Limit to 1 response" is deliberately *off* (members may want to resubmit if circumstances change); "Verified email" stays *on* so sign-in remains mandatory and per-user deduplication still works on the slug.

Editing static page copy

1. `git checkout -b copy/<short-description>`
2. Edit the relevant `*.html` file.
3. Preview locally: `python3 -m http.server 8000` → open `http://localhost:8000`.
4. Open a PR. Merge once reviewed.

GitHub Pages rebuilds in ~30 seconds after merge.

Cutting a release

The repository follows **Semantic Versioning 2.0.0** from `v1.0.0` onwards. The full convention (what MAJOR / MINOR / PATCH mean for a website + directory + docs deliverable) is in `README.md` → "Versioning"; the running history is in `CHANGELOG.md` at the repository root.

A release is cut whenever a milestone is worth marking — typically at the close of a sprint of substantive work, or after a noteworthy fix. The mechanics are wrapped in `scripts/release.sh` so the whole sequence is a single command:

1. While the work is being merged, accumulate notes in the `[Unreleased]` section of `CHANGELOG.md` via each PR. Keep the format consistent (subheadings such as *Added*, *Changed*, *Fixed*, *Security*).
2. When ready to release, ensure local `main` is in sync with `origin/main`, then run:

```
scripts/release.sh 1.1.0          # the version number you're cutting
scripts/release.sh 1.1.0 --dry-run # preview, change nothing
```

3. The script performs a pre-flight check (must be on `main`, clean tree, in sync with origin, tag not yet used), promotes `[Unreleased]` to `[1.1.0] · YYYY-MM-DD`, resets a fresh `[Unreleased]`, updates the compare-link block, commits, pushes, creates an annotated `v1.1.0` tag on the new commit, pushes the tag, and finally calls `gh release create` with the changelog body as the release notes.
4. On release day the script also runs `scripts/promote-roadmap.py` (added v1.7.0), which flips matching cards on the public roadmap from *planned* to *shipped* across `/roadmap.html`, `/roadmap.fr.html` and `/roadmap.de.html` in one pass.
5. If the version being cut is a minor or major release, the script prints a **PDF cover-bump reminder** at the end: a nudge to refresh the version stamp on this pack's cover and rebuild. Patch releases skip the reminder.
6. Before exiting, the script lists any **open issues tagged with the milestone** being cut. This is a sanity check, not a block: it is normal for some issues to roll forward to the next milestone, but seeing the list ensures nothing was meant to be in this release and silently slipped.

Pre-conditions

- `gh` CLI installed and authenticated against `EISSeuropa/netsec.github.io`.
- You can push to `main` (no branch-protection rule blocking direct push for release commits).
- The work that is *in* the release is already merged to `main`.

For changes that warrant a documentation-pack refresh, also bump the version stamp on the cover and run `./docs/pdf/build.sh` before tagging. The PDF carries its own version stamp on the cover and its own changelog in Appendix D — the two version axes are independent for historical reasons (see the v1.3.0 entry of this pack's own changelog appendix).

The Grants page in practice

FUNDING & SUPPORT

Grants & Calls

NetSec funds five types of networking grants to support mobility, conference participation, and virtual collaboration across European security studies. Calls are open to the wider research community, not just Action participants, see each grant's eligibility for details.

Early-career researchers may also want the [NetSec Training School](#), which funds PhD participants' travel and mentoring alongside the conference.



Applications go through [e-COST](#), sign in and select Action CA24154. **Only the five schemes below are funded by NetSec.** Other grant types you may see in the portal aren't, and will be rejected if applied for.



MOBILITY

Short-Term Scientific Mission (STSM)

Supports a working visit to a host organisation in another country, for specific research carried out over a defined period, collaborating, using facilities, building new partnerships. The host must be in a different country than the applicant's.

AMOUNT

€ 2 100

ACTIVITY

In-person visit
to a host in another country

LOCATION

Anywhere
worldwide

ELIGIBILITY

- Open to anyone **affiliated in a COST Member country or NNC**, regardless of career stage.
- The **host organisation must be in a different country** than the applicant's affiliation.
- The visit supports the Action's objectives *and* the applicant's career development.
- Up to **50 % advance payment** may be released after awarding (STSM only, other grant types pay in full after the activity).
- If two or more STSM grantees share the same host, they must submit **original** (non-identical) scientific reports.

Looking for a host? [Filter the directory by STSM hosting](#) to find members whose institution can host a visit.

GETTING YOUR VISIT READY

- Hosting a visitor? Download the [host invitation-letter template](#) and adapt it on your institution's letterhead.
- Current STSM collection dates are published on [e-COST](#).

[Apply on e-COST](#)



MOBILITY

Virtual Mobility Grant (VM)

The virtual counterpart of an STSM, structured collaboration with a host organisation in another country, conducted online. Same goals (research partnership, career development, achieving the Action's objectives), no travel.

AMOUNT

€ 1 300

ACTIVITY

Virtual collaboration
with a host in another country

LOCATION

Worldwide
online, no travel

ELIGIBILITY

- Open to anyone **affiliated in a COST Member country or NNC**.
- Collaboration with a host in a **different country** than the applicant's affiliation.
- The deliverable benefits both the grantee and the Action.

[Apply on e-COST](#)



CONFERENCE GRANT

Young Researcher and Innovator Conference Grant

For **Young Researchers and Innovators** (under 40 at the time of application) to present their own research, either as an oral talk or a poster, at a conference within the Action's scope. Builds visibility for the next generation of European security scholars.

AMOUNT € 1 200	ACTIVITY Oral or poster your own work	LOCATION Anywhere face-to-face or virtual
--------------------------	--	--

ELIGIBILITY

- Action participants, **under 40 years old** at the time of application.
- Accepted to present (oral or poster) own work within the scope of the Action.
- Affiliated in any participating country.
- No overlap with another COST grant or meeting for the same activity.

On the e-COST portal, this application is visible only to applicants under 40.

[Apply on e-COST](#)

CONFERENCE GRANT

Inclusiveness Target Country Conference Grant

Supports researchers based in **Inclusiveness Target Countries** (ITCs) to present *their own* work, within the scope of the Action, at an external conference. The goal is to widen geographic participation and help individual careers along the way.

AMOUNT € 1 200	AVAILABLE 4 grants across the Action	ACTIVITY Oral presentation of your own research	LOCATION Anywhere face-to-face or virtual
--------------------------	---	--	--

ELIGIBILITY

- Action participants **affiliated in ITCs or Near Neighbour Countries**.
- Accepted to give an **oral presentation of your own work**, within the scope of the Action.
- No overlap with another COST grant or meeting for the same activity.

On the e-COST portal, this application is visible only to applicants affiliated in an ITC.

[Apply on e-COST](#)

CONFERENCE GRANT

Dissemination Conference Grant

Supports an Action participant who is presenting **the Action's results** (its work, activities, or collective findings) at an external conference, boosting NetSec's visibility, attracting new participants, and disseminating outputs to the wider field.

AMOUNT € 1 250	ACTIVITY Oral presentation of the Action's work	LOCATION Anywhere face-to-face or virtual
--------------------------	--	--

ELIGIBILITY

- Action participants **affiliated in COST Member countries or Near Neighbour Countries (NNCs)**.

Figure 17 · Grants & Calls. All five NetSec grant schemes, with per-grant e-COST deep links and a vertical awarding-process timeline further down the page.

Escalation

SYMPTOM	FIRST PORT OF CALL
Site returns 404 / 500	githubstatus.com
Sync workflow fails	The <i>CI alarm</i> issue the failure alarm assigned to you links the run. Open it and scroll to the red step.

SYMPTOM	FIRST PORT OF CALL
Form submissions stop arriving	Formspree dashboard
New bio doesn't appear after the daily sync	Check Google Sheet (row present? consent ticked?) → manually trigger <i>Sync member bios</i>
Suspected security issue	Follow SECURITY.md — do not open a public issue
DNS / domain issue	Registrar admin; GitHub Pages settings as sanity check

Handover checklist

The branch-protection ruleset's bypass is keyed to the repo `Admin` role, so the role transfer needs care — get it wrong and `release.sh` stops working until a re-grant. The full version is in [docs/admin-guide.md](#); the headline items:

Access grants — new admin

- Add them to the `EISSeuropa` org with the `Admin` role on this repo (*not* `Maintain` or `Write`). The `Admin` role is what permits the `release.sh` bypass against `protect-main`.
- If a second person stays on as a non-release-cutting maintainer, give them `Maintain` separately — the `Admin` role is for the release-cutter only.
- Grant them ownership of the Google Form + linked Sheet.
- Grant them access to the Formspree project.
- Make sure they have edit rights to the DNS registrar entry at Namecheap.

Automation handover

- Provision a fresh fine-grained PAT in the new admin's name with these repository permissions: `Contents: read+write`, `Pull requests: read+write`, `Issues: read+write`, `Workflows: read+write`, `Administration: read+write`.
- Verify the new PAT works by listing rulesets: `gh api /repos/EISSeuropa/netsec.github.io/rulesets`.
- **Downgrade Administration to Read**. Steady-state automation does not need write. The ruleset bypass that lets `release.sh` push the changelog-promotion commit through `protect-main` is keyed to the user's *repository role* (`Admin`), not to the PAT's `Administration` permission — so the release pipeline continues to work unchanged. Read-only access still allows `gh api .../rulesets` for future verification. Re-grant `read+write` temporarily only when a ruleset adjustment is needed (and prefer the GitHub UI for one-off tweaks).
- Revoke the previous admin's PAT immediately after the new one is verified.

Verification

- Walk the new admin through this document and the markdown reference under `docs/`.
- Have them run `scripts/release.sh 0.0.0 --dry-run` from a synced `main`. The pre-flight should report *"✓ On main, clean, in sync with origin, v0.0.0 is fresh"* and stop there. A dry-run changes nothing.
- Have them visit [Settings](#) → [Rules](#) → [Rulesets](#) and confirm both rulesets are listed as *Active*.

Revocation — previous admin

- Remove the previous admin's repo access. Their bypass capability against `protect-main` disappears the moment their `Admin` role is removed — GitHub re-checks on every push, no caching to worry about.
- Remove or downgrade their org membership per Action policy.
- Update the *Owner / login* column in the accounts table with the new owner.

07 Security & DevSecOps

Threat model, disclosure policy, GitHub-native automation, supply-chain and operational hardening.

Security is treated as a continuous practice rather than a one-time review. The full coordinated-disclosure policy lives in [SECURITY.md](#) at the repository root; this chapter summarises what is in place, what is automated, and what is the responsibility of the human admins.

Threat model in one paragraph

The site is a **static HTML deployment** with no server-side code, no database, and no authenticated user surface. The classical injection bug-classes (SQL, RCE, deserialisation, SSRF) do not apply because nothing on the server interprets user input. The realistic risk surface narrows to four areas: **(1)** the contributor pipeline — a compromised GitHub account with push access, **(2)** the two sync workflows pulling data from external sources, **(3)** the third-party processors we depend on (Formspree, Google, GitHub Pages itself), and **(4)** personal data we hold in [data/bios.json](#). The controls below are sized for that surface.

Coordinated-disclosure policy in brief

The shape of [SECURITY.md](#):

Scope

In scope: the current [main](#) branch, the deployed site at [netsec-cost.eu](#), the two GitHub Actions, the Python sync scripts, and any personal data we hold.

Out of scope: older branches, tags, or forks; reports about COST or EU branding; volumetric DoS against third parties (GitHub, Formspree, Google). Those go to the relevant vendor.

How to report

Two private channels, never a public GitHub issue:

1. **GitHub Security Advisories** (preferred):
github.com/EISSeuropa/netsec.github.io/security/advisories/new.
2. **Email** the maintainer; for data-protection matters specifically, contact the Data Controller (Universiteit Leiden) per the addresses listed in [privacy.html](#).

What to expect

STAGE	TARGET
Acknowledgement	Within 5 working days.

STAGE	TARGET
Initial assessment	Within 14 working days.
Resolution — Critical	Patch in days; hotfix to <code>main</code> .
Resolution — High / Medium	Next sprint, typically 2–4 weeks.
Resolution — Low	Routine maintenance.
Disclosure	Coordinated; credit on request.

Safe harbour

Good-faith research is welcomed: act only against your own data and the public site, avoid privacy violations and service disruption, do not retain personal data of others, and give us reasonable time to fix before public disclosure.

GitHub-native security automation

The repository is enrolled in five GitHub Advanced Security features. They run continuously, with results visible under the *Security* tab.

FEATURE	TRIGGER	WHAT IT DOES
Private vulnerability reporting	Researcher submission	Offers external reporters a confidential channel inside GitHub, with end-to-end encryption and the option to collaborate on a fix in a private fork before public disclosure. Replaces the older "find an email address" route.
Security advisories	Maintainer-initiated, post-triage	Records every confirmed vulnerability as a draft advisory, links it to the fix commit, and publishes a CVE when warranted. Provides a single audit trail for evaluators.
Dependabot alerts	Continuous	Scans the dependency graph (Python <code>requirements.txt</code> , GitHub Actions versions) against the GitHub Advisory Database. Opens an issue per advisory with an upgrade path.
Code scanning — CodeQL	<code>push</code> + <code>pull_request</code> against <code>main</code> , plus a weekly cron	Runs the security-and-quality and security-extended CodeQL query suites at the <i>high-precision</i> setting, across HTML, JavaScript, Python, and GitHub Actions YAML. Findings appear as PR review comments and on the Security tab.
Secret scanning + push protection	Every push and historical sweep	Detects exposed tokens, API keys, and high-entropy strings matching known provider patterns. Push protection blocks the commit at <code>git push</code> time before the secret enters history.

Why this combination, on a static site

The site itself has almost no executable code, but the *sync* workflows execute trusted Python with broad repo-write capabilities. Treating the build pipeline as a first-class security target, rather than just the deployed pages, is what these five tools collectively achieve.

Supply-chain and CI hardening

- **Pinned third-party Actions.** All `uses:` references in `.github/workflows/` are pinned to a full commit SHA, with the version in a trailing comment, so an upstream tag retag cannot inject new code without our review. Dependabot proposes each bump as a PR.
- **Least-privilege `GITHUB_TOKEN`.** Each workflow declares the narrowest `permissions:` block it needs (`contents: write` for the sync jobs, `contents: read` elsewhere). The default token is read-only at the repository level.
- **Protected `main`.** Every change, the sync workflows' included, reaches `main` through a pull request, and a ruleset holds the merge until the required checks pass (CodeQL, the link checker and the drift gates). The bios and cost.eu PRs, which change member data, also wait for the maintainer to merge them.
- **No long-lived deploy keys.** Deployment is handled by GitHub Pages itself, using the repository's own short-lived OIDC token, so there is no external secret to rotate.
- **Version-controlled data.** Both data files (`data/bios.json` , `data/mc-members.json`) are version-controlled. Any malicious or accidental change is one `git revert` away.

Branch and tag protection (GitHub rulesets)

Two repository rulesets enforce the boundary between routine and catastrophic operations on this repo. Together they guard against the classes of change that would otherwise bypass review — rewriting `main`'s history, deleting the deployed branch, or silently re-pointing a published version tag.

RULESET	TARGET	WHAT IT ENFORCES	BYPASS
<code>protect-main</code>	Default branch (<code>main</code>)	Restricts deletions; restricts force-pushes (no bypass); requires linear history; requires a pull request before merging; requires conversation resolution; restricts merge methods to <i>squash</i> ; requires all four CodeQL status checks (<code>CodeQL</code> , <code>Analyze (actions)</code> , <code>Analyze (javascript-typescript)</code> , <code>Analyze (python)</code>) to pass.	Repository Admin , always. Allows <code>scripts/release.sh</code> to push the changelog-promotion commit directly while still blocking everyone else.
<code>protect-release-tags</code>	Tags matching <code>v*</code>	Restricts deletions, updates, and non-fast-forward updates. Once a release tag is published it cannot be moved or deleted via normal operations.	None — not even admins. To genuinely correct a mis-tagged release, the ruleset must be temporarily disabled from the UI. The friction is the point.

Why these two rules, in this shape

The threat model singles out four catastrophic moves: force-pushing `main`, deleting `main`, deleting a published tag, and silently re-pointing a published tag. The first three are hard-blocked outright. The fourth (silent re-tagging) is the most insidious — a third party with write access could move `v1.0.0` to a different commit without leaving any auditable trace beyond the tag's own reflog. Restricting *tag updates* entirely, with no bypass, makes that class of change physically impossible without first toggling the ruleset off in the UI.

All other operations route through the normal pull-request + CodeQL flow.

Both rulesets are visible at [Settings → Rules → Rulesets](#); their JSON definitions are stored in the repo's GitHub configuration (not in the working tree) and can be exported via `gh api /repos/EISSeuropa/netsec.github.io/rulesets`.

Web-platform hardening

- **HTTPS everywhere.** GitHub Pages enforces HTTPS with an auto-renewed Let's Encrypt certificate. Plain-HTTP requests are redirected.
- **Strict-Transport-Security.** GitHub Pages sends a long-lived `Strict-Transport-Security` header on every response.
- **No inline secrets, no privileged scripts.** The only JavaScript on the site is the locally-hosted `assets/js/site.js`; no third-party tag managers, analytics, or chat widgets are loaded.
- **Minimal third-party calls.** At runtime the page contacts Google Fonts (CSS only), FlagCDN (PNG only), and Formspree (only on form submit). All declared in `privacy.html`.
- **SafeHTML form handling.** The contact form posts via HTTPS to Formspree; we never echo submitted content back into a page, so there is no XSS surface from the form.

Account and access hygiene

- **Two-factor authentication** is required on every account with push access via GitHub's org-level 2FA enforcement.
- **Maintain role, not Admin,** for routine collaborators. The *Admin* role is held only by accounts that genuinely need branch-protection or settings access.
- **Defence-in-depth on handover.** The admin handover checklist (Section 06) ends with revoking the previous admin's access; nobody keeps access "just in case".
- **Branch and tag protection** enforced via GitHub rulesets — see the dedicated section above. The `Admin` role is what grants the release-cutter their bypass against `protect-main`, so it is treated as a distinct, sparingly-granted role, separate from the routine `Maintain` permission.

Personal-data minimisation

The site holds minimal personal data: name, institution, country, working group(s), a short bio, optionally a photo and links. There is no email address in `data/bios.json`; the contact form is the only mechanism for reaching a member, and it is mediated by Formspree under a Data Processing Agreement. All processing

terms are spelt out in [privacy.html](#) ; the lawful basis is consent, captured at form submission time and revocable by request.

Audit trail

Every meaningful change to the site is a commit on [main](#) . Every commit links to a pull request, every pull request to the GitHub Actions run that built and deployed it, and every Security-tab event (alert, advisory, scan) timestamps an attributable user. The repository's *Insights* tab gives a single view of contributors, dependency health, and traffic.

A Appendix · Accessibility standard & assessment

What we target, how we test, what we found, and how to flag a barrier.

The full statement lives at netsec-cost.eu/accessibility.html and is the authoritative version. This appendix summarises it for evaluators reading offline.

Standards and legal framing

ASPECT	POSITION
Target conformance	WCAG 2.1 Level AA — Web Content Accessibility Guidelines, Level AA success criteria.
European harmonisation	Aligned with EN 301 549 , the European accessibility standard for ICT products and services.
Legal framework	Web Accessibility Directive 2016/2102 (EU). Each EU Member State designates its own enforcement body.
Current status	<i>Partially compliant.</i> The majority of WCAG 2.1 AA success criteria are met; the limitations listed below are tracked for a future iteration.
Statement version	v1.0 · prepared 14 May 2026 · next scheduled review 14 May 2027.

Latest self-assessment

An automated audit was performed on **14 May 2026** with [axe-core 4.10.2](#) running against every section of the home page (with all collapsible regions expanded). Results:

0	50	1
Violations	Passes	Needs manual review

The single item flagged for manual review is colour contrast on text rendered over `backdrop-filter` glass surfaces — axe-core cannot evaluate this automatically because the perceived contrast depends on what's behind the surface. Manual spot-checks confirm these surfaces meet WCAG 2.1 AA contrast in both light and dark mode.

Test methodology

The statement was prepared by self-assessment using three complementary methods:

- **Manual review** of semantic HTML, keyboard navigation, focus management, and tab order — every page walked through with the keyboard alone.
- **Automated scans** with [axe-core 4.10.2](#) against the home page with all collapsible regions expanded.
- **Manual contrast spot-checks** on glass surfaces in both light and dark mode (the one case axe-core cannot evaluate).

We re-assess after material changes to the design system or content structure, and at a minimum once per year.

Features in place

A non-exhaustive list of the accessibility affordances the site already ships:

- Semantic landmarks (`<header>` , `<nav>` , `<main>` , `<footer>`) and a clean heading hierarchy without level jumps.
- Skip-to-content link, visible on keyboard focus.
- Visible `:focus-visible` ring on every interactive control.
- `alt` text on every image; explicit `<label for>` association on every form input.
- Light and dark themes with a manual toggle; OS-level `prefers-color-scheme` as the default.
- `prefers-reduced-motion` disables decorative animations.
- The *Management Committee by Country* directory uses a native `<details>` accordion — fully keyboard- and screen-reader-accessible without bespoke ARIA wiring. Deep-links to specific country cards auto-expand the section.
- The roadmap Gantt grid uses ARIA grid roles (`role="table"` , `role="row"` , `role="columnheader"` , `role="cell"`) so assistive technology parses it as tabular data.
- Working-group chips are grouped with `role="group"` and an `aria-label` so screen readers announce them as a group rather than as loose tokens.
- Contact form: inline validation, accessible error reporting, and a confirmation toast announced via `role="status" aria-live="polite"` .

Known limitations

The following parts of the site do not yet fully meet WCAG 2.1 AA, or have constraints worth flagging:

- **Roadmap Gantt chart.** A dense data visualisation. On narrow viewports the chart requires horizontal scrolling; the scroll region is keyboard-focusable so users can pan with arrow keys (WCAG 2.1.1), but a text-only alternative summary is not yet provided.
- **Decorative animations.** Aurora background blobs and reveal-on-scroll fades are automatically disabled when the OS or browser signals `prefers-reduced-motion` . We do not currently expose a separate per-site override.

- **Third-party assets.** Country flag thumbnails are served from flagcdn.com and member headshots from the GitHub Pages CDN. Long-term availability is outside the Action's direct control; if any image becomes unavailable, the surrounding text content remains intact and informative.
- **EU emblem SVG.** The *Funded by the European Union* emblem carries an `aria-label` and `role="img"` but no long description; it is described by the surrounding boilerplate text.

Reporting a barrier

If you encounter an accessibility barrier on this website, or need any of its content in an alternative format, please get in touch:

- Email the Action Chair, Dr Moritz Weiss — moritz.weiss@gsi.lmu.de
- Or use the [contact form](#) and mention *"accessibility"* in your message.

We aim to respond within **10 working days**.

Enforcement procedure

If you are not satisfied with our response, you may contact the equality body or accessibility-compliance body in your country. Within the European Union, each Member State designates its own enforcement body under the [Web Accessibility Directive 2016/2102](#).

B Appendix · Licensing

The dual MIT + CC BY 4.0 model and suggested attribution.

The repository uses **dual licensing**, matching EU and COST open-access norms: code is permissively licensed for any reuse, content is openly licensed with an attribution requirement.

WHAT	LICENCE
Source code (HTML / CSS / JS, Python, GitHub Actions)	MIT
Site content (prose, page copy, documentation)	CC BY 4.0
Member bios and photographs	© contributors, used with consent
Third-party assets (icons, fonts, flags, COST / EU)	Their own licences — see LICENSE-CONTENT

Suggested attribution when reusing site content:

"Based on content from COST Action NetSec (CA24154), <https://netsec-cost.eu>, CC BY 4.0."

Where reusing the source code, an MIT-style attribution in your own [LICENSE](#) or [NOTICE](#) file is sufficient.

Why two licences

Source code and prose travel through different reuse channels. A permissive code licence (MIT) lets anyone fork the project and adapt the templates without an attribution wall in their UI; a content licence (CC BY 4.0) gives written work the standard open-access treatment expected by COST and the European Commission. Keeping them separate avoids accidentally over-licensing either side.

C Appendix · Promotional poster

An outward-facing A3 summary of the Action, ready for print and reuse.

The poster on the following page is the Action's **outreach-ready summary**. Where the internal poster after the cover (Section "NetSec at a glance") is sized for stakeholder reading inside this pack, this one is sized for **A3 portrait print** and designed for display: conference poster sessions, training-school noticeboards, departmental corkboards, and similar venues where someone will glance at it for ten seconds and want to leave with a URL.

Its content tracks netsec-cost.eu at **v1.1.0**: the eight headline features, the directory's running numbers (30 countries, 49 MC members, four Working Groups, five grant schemes), a mock of the searchable Network directory, and a scannable QR code resolving to the home page. The funding-statement strip at the foot carries the COST and EU emblems together with the standard *Funded by the European Union* attribution.

Source & reproduction

The source HTML is version-controlled at docs/promo/poster-promo.html ; the rendered raster used in this appendix lives at docs/pdf/poster-promo.png (2480 × 3508 px, A3 portrait at ~192 dpi). To re-render after editing the HTML — e.g. when the running numbers change — run a headless Chrome capture from the repository root:

```
/Applications/Google\ Chrome.app/Contents/MacOS/Google\ Chrome \  
  --headless --disable-gpu --hide-scrollbars \  
  --virtual-time-budget=12000 \  
  --window-size=1240,1754 \  
  --force-device-scale-factor=2 \  
  --screenshot=docs/pdf/poster-promo.png \  
  "file://$(pwd)/docs/promo/poster-promo.html"
```

Then re-run `./docs/pdf/build.sh` to refresh this PDF.

Where it is used

- **This documentation pack** — embedded on the following page as the second half of Appendix C, so the pack itself doubles as a delivery vehicle for the poster.
- **Conference and training-school print runs** — A3 portrait prints distributed at events where NetSec members present or recruit.
- **Departmental noticeboards** — at participating institutions, especially those of MC members in early stages of building local working groups.
- **The members' Wiki press kit** — see [the Wiki](#); the rendered PNG is suitable for use as an attachment, a slide-deck cover, or a banner image.

- **Email outreach** — as an attachment to open-call communications and welcome emails to nominated MC representatives.
- **Annual reporting to COST** — as visual evidence of the Action's communication outputs.

What *not* to do with it

- Do not crop the funding-statement strip out — the COST and EU acknowledgement is a contractual requirement on derived communications.
- Do not edit the SPDX or licensing text in place. The licensing posture lives in `LICENSE` and `LICENSE-CONTENT` at the repository root; the poster carries no licence chip of its own by design.
- Do not use the poster as the Open Graph / social-share image for the website. OG images need a 1200 × 630 landscape format; the poster is A3 portrait. The OG image at `assets/images/og-image.png` remains the canonical share card.



• DELIVERABLE D1 • OPEN COMMUNITY DIRECTORY

Networking European security knowledge.

AIM OF THE ACTION European security research is scattered across borders, institutions and disciplines. **NetSec connects this dispersed community into one open, pan-European network** — so scholars across 30+ countries can share knowledge, train the next generation, and build a more inclusive and representative field. This site is its public face and open directory.

FOUR WORKING GROUPS

</working-groups.html>

WG1 63 members Building the Network LEAD Dr Moritz Weiss	WG2 49 members Transfer of Knowledge LEAD Dr John Helferich	WG3 65 members Fostering the Next Generation of Scholars LEAD Dr Chiara Ruffa	WG4 32 members Inclusion, Representativeness & Ethics LEAD Dr Rebecca Pediti
--	---	---	--

FEATURES

[netsec-cost.eu](#) · v1.10.0

 Multilingual English authoritative; French and German variants in beta with hreflang.	 Accessible EN 301 549-aligned; zero axe-core violations on the home page.	 Mobile-responsive Reflows cleanly from 4K screens down to a 320 px phone.	 Searchable Site-wide full-text search across every page and member, keyboard-first.
---	---	---	---

THE DIRECTORY IN NUMBERS

[data/bios.json](#) · updated weekly

30 COUNTRIES	49 MC MEMBERS	4 WORKING GROUPS	5 GRANT SCHEMES	~51% WOMEN ON MC	3 UI LANGUAGES
------------------------	-------------------------	----------------------------	---------------------------	----------------------------	--------------------------

THE NETWORK · A DIRECTORY YOU CAN ACTUALLY SEARCH

</people.html>

Find a member ↗

[netsec-cost.eu/people](#)

All WG1 WG2 WG3 WG4

Dr Arthur Laudrain
ETH Zürich ·
MC WG1 WG3

Dr Marie Robin
Leiden University ·
Vice-Chair WG2 WG3

Mr Eugenio Sánchez
Sciences Po Paris ·
Sci-Comm WG3

Prof Filip Ejodus
U. of Belgrade ·
WG1 co-lead WG4

Search × WG/MC chip × country, all **AND-combined**. 49 members · 30 countries

JOIN THE NETWORK

Open call for bios. Always on.

Anyone working in or alongside European security studies can submit a profile. Required-consent form, weekly review on GitHub.

[Submit a bio](#) →

[Browse the directory](#)



VISIT · REUSE · CONTRIBUTE

netsec-cost.eu

Scan to open the directory.



FUNDED BY
the European Union

Views are those of the Action only and not those of COST or the EU

D Appendix · Changelog

What each revision of this documentation pack records — kept last so the most recent revision is the final page.

This changelog tracks the documentation pack itself, not the website. Website history is in `git log` on `main` and in [the repository's own CHANGELOG.md](#); documentation-pack versions are stamped on the cover and follow **Semantic Versioning 2.0.0** from v1.0.0 onwards. The current revision gets a full lede + themes + index treatment; older revisions are compressed to a single paragraph each so the appendix stays scannable as the release history grows.

v1.13.2 · October 2026 · Automation catch-up

Pack-only revision correcting the automation described across Sections 02, 06 and 07, which had fallen behind the workflows. The roadmap autostamp (Figure 9) is the daily `roadmap-refresh.yml`, which replaced `sync-roadmap.yml` and also refreshes milestone progress. The bios sync runs daily, `sync-cost.yml` joins the sync table, and Figure 16 separates the bios and cost.eu PRs, which the maintainer merges by hand, from the Indico and roadmap PRs, which merge on green checks. The security section no longer claims a two-person review. Third-party Actions are recorded as SHA-pinned.

The social pipeline (Figure 10) posts to LinkedIn as well as Bluesky, the spotlight runs on Tuesdays at 10:00 Paris time, and news enters by PR, since the issue-driven news publisher was removed. The new failure alarm, which files an assigned issue when a scheduled workflow fails, appears in Section 02 and in the escalation table. The website version on the cover moves with the next release.

v1.13.1 · August 2026 · Figure numbering

Every figure is renumbered in document order, one to seventeen. Two numbers were used twice (the About page and the end-to-end stack were both Figure 2, the Directory and the type-pairing plate both Figure 10), and the social and OG-card diagrams carried 13 and 14 while sitting eighth and ninth on the page, so a reader following a number could reach the wrong plate with nothing to tell them. The changelog entries below that point at a figure follow the new numbers, since they point at figures the document still contains: the page graph is Figure 4 and the Network Map is Figure 14. Captions only, no content change.

v1.13.0 · August 2026 · Section-level catch-up to website v1.13.0 and v1.14.0

Closes the catch-up the two previous revisions deferred. Section 02's page graph (Figure 4) and inventory gain the four pages added since the last section pass: the NetSec Network Map (`network-map.html`), the Working Group 2 policy-workshop page (`policy-workshop-2026.html`), the slide-templates gallery (`slides.html`) and the parked `essc-2027.html`, taking the count from eighteen to twenty-two. The Network Map is drawn with two arrows converging on it rather than one from the nav, which is how it is actually reached, and the parked page is named in the prose and left out of the graph.

Section 04 gains *What the deploy builds*, describing the change that removed 582 machine-written files from the repository: the 84 Open Graph cards, the 252 profile pages and the `?v=` cache-bust tokens are built by the Pages deploy in a fixed order, each build step is followed by a count assertion against `data/bios.json`, and the drift gates that guarded the committed artefacts are retired. The pack previously described those files as committed and gated. Member photographs stay committed, and the section says why.

All five site screenshots were re-captured, and a sixth was added: Figure 14, the Network Map.

`docs/pdf/build.sh --shots` captures it alongside the others now. Worth knowing for whoever reads the filenames next: `snap-network.jpg` is the Directory, named before the Network Map existed, and the Network Map is `snap-map.jpg`.

v1.12.2 · August 2026 · Cover bump for website v1.13.0 and v1.14.0

Cover bump spanning two website releases. [v1.13.0](#) rebuilt the Directory's mentorship matching around a guided sentence, added LinkedIn beside Bluesky on the social pipeline, and took an editorial design pass over the type scale and the home hero. [v1.14.0](#) brought the NetSec Network Map to Beta at [/network-map.html](#) in three languages, with search, zoom, hub panels, a keyboard path and a table of everyone it draws, and it filed the last twenty-nine research keywords that reached no research theme.

Section-level catch-up is deferred to the next pack revision, and this is the second bump to defer it. Section 02's page graph and inventory do not yet carry the Network Map or the Working Group 2 policy-workshop page, Section 04 does not describe the move of generated files to deploy time, and the five figures are the July captures. Tracked for the next revision.

v1.12.1 · July 2026 · Post-conference section catch-up and TOC page numbers

Pack-only revision closing the section-level catch-up the [v1.12.0](#) addendum deferred. Section 02 now carries the post-conference surface: the page graph and the inventory gain the Events page ([events.html](#)) and the generated per-member profile pages at [people/<slug>.html](#) (177 pages from 59 members at the time of writing), with the hand-authored page count moving to eighteen and the generated profiles counted separately. Section 04's repository layout catches up on the same scope, on two pages it had missed earlier ([working-groups.html](#), [summer-school.html](#)), and records the shared [assets/js/people-directory.js](#) renderer, the [data/orcid-works.json](#) publications cache, and [scripts/build-profile-pages.py](#). The table of contents now carries a page number per section, completing the structural improvement first queued in [#229](#). This build is also the first PDF to include the news/social and OG-card pipeline sections with Figures 13 and 14, which had landed in the HTML source after the previous build. Site screenshots were re-captured from the live worktree.

v1.12.0 · June 2026 · Section-level catch-up to website v1.11.0 and v1.12.0

Cover bump and section-level catch-up spanning website [v1.11.0](#) ("Directory filters, mentorship, and a smoother mobile directory") and the [v1.12.0](#) work cut alongside this pack. [v1.11.0](#) gave the directory a research-theme filter and a mentorship axis, rebuilt the mobile filter sheet as a native top-layer `<dialog>` for Safari-grade responsiveness, and laid the groundwork for the founding cohort. The [v1.12.0](#) cycle adds a dedicated NetSec Summer School page ([/summer-school.html](#) + FR + DE), run jointly with EISS, whose faculty roster resolves member headshots live from the directory by name and whose partner block embeds the EISS lookup as an inline SVG. The member-card popover that the ESSC programme and the directory share is now a single `window.netsecMemberCard` component rather than a copy per page, and the same first-and-last name matcher now also heals the About-page and Working-Group leadership cards, so a card gains its live headshot the first time the person appears in the directory. A quiet "Founding contributor" badge marks the 52 founding proposers on directory cards, computed at sync time from [data/founding-proposers.json](#), with the founding figures (52 contributors across 21 countries) added to About and the press kit. This revision adds [summer-school.html](#) to the page graph (Figure 4) and the page inventory and bumps the page count to seventeen, and records the shared member-card component and the founding badge. Site screenshots were re-captured from the live worktree.

Post-conference addendum: the [v1.12.0](#) release grew well beyond what this pack captures, gathering the work merged once the Summer School and the European Security Studies Conference were over. The directory gained real shareable profile pages at [/people/<slug>](#) with their own `Person` structured data, an STSM-

hosting signal tied to the grants page, ORCID-fed recent-publications lists on cards, and a mentorship matching panel that pairs offers with requests inside the active filters. A dedicated Events page (`/events.html` + FR + DE) now gathers every NetSec event in one place, the About page opens with an "In numbers" strip, and the conference pages settled into a fixed archive once Stockholm closed. The bare "MC" abbreviation was spelled out as "Management Committee" across the reader-facing copy, and the triplicated directory renderer became one shared `assets/js/people-directory.js` module. Section-level catch-up for this post-conference scope (the new pages in the Section 02 page graph and inventory, the shared renderer in Section 04) was deferred to the next pack revision and completed in v1.12.1 above.

v1.10.0 · May 2026 · Section-level catch-up to website v1.10.0

Cover bump and section-level catch-up to website [v1.10.0](#) ("Working Groups page and milestone-aware roadmap"), cut just before the European Security Conference. The headline is a dedicated Working Groups page (`/working-groups.html` + FR + DE) rendering each group's objective, leadership, and live membership from a new `data/wg.json` surface the weekly cost.eu sync writes ([#378](#)), with the Memorandum-of-Understanding titles adopted site-wide and Events cross-linked to the groups they serve in both directions. The public roadmap reads its own GitHub milestones, showing a progress bar per in-flight release and auto-marking the next one in progress. The conference run-up adds non-presenting co-authors to the ESSC programme, an *At a NetSec conference* FAQ section, a one-click programme PDF, and a chain of print-to-PDF fixes, while the directory keyword pipeline folds American spellings to British English and the weekly member-spotlight engine landed dormant. This revision also refreshes the sections: Section 02 adds `working-groups.html` to the page graph (Figure 4) and the page inventory and bumps the page count to sixteen, and Section 04's repository layout records the two new data surfaces (`data/wg.json` , `data/roadmap-progress.json`) and the `sync-cost.py` fourth output. Site screenshots were re-captured from the live worktree. This closes the section-level catch-up tracked at [#229](#).

v1.9.4 · June 2026 · Cover bump for website v1.9.0

Cover-only bump matching website [v1.9.0](#) ("Pre-Stockholm calendar plumbing"), four days before the Summer School and European Security Conference open at Stockholm University. Records the gap to that release: per-event `.ics` downloads now live at `/calendar/<slug>.ics` alongside the aggregate subscribable feed; the home-page event cards derive at runtime from `data/events.json` across all three locales (events-from-JSON refactor, [#249](#)) and each card carries an *Add to calendar* dropdown with Google / Outlook / Apple webcal / direct `.ics` destinations; the home-page news cards mirror the same pattern from a new `data/news.json` , with an RSS 2.0 feed at `/news.xml` exposed for academic and policy aggregators (Feedly / Inoreader / NetNewsWire) via `<link rel="alternate">` auto-discovery plus a visible subscribe affordance under the news block. Card descriptions get a five-line clamp with a locale-aware *Read more* toggle. Section-level content not refreshed in this revision; section-level catch-up to website v1.9.0 (Section 02 repo layout adding `scripts/build-news-rss.py` + the `calendar/` directory + the new renderers, Section 04 architecture for the runtime-render-from-JSON pattern, the table-of-contents page-numbers structural improvement) remains queued for the next substantive section-level catch-up. Tracked at [#229](#).

v1.9.3 · May 2026 · Cover bump for website v1.8.0

Cover-only bump matching website [v1.8.0](#) ("Brand launch, Indico writes, programme PDF, voice sweep"). Records the gap to that release: the designer's four-petal NetSec mark and lockup are now deployed across all 46 site pages (header, favicon family, OG card, JSON-LD logo), two new operational scripts (`scripts/indico_patch.py` and `scripts/indico_clean_duplicate.py`) handle Indico write-side automation and the ESSC-N to ESSC-N+1 rollover, the programme page exports a self-identifying PDF with cover masthead and running header, the bios-sync and cost-sync workflows notify the maintainer when an auto-PR opens, and the CLAUDE.md §7 writing-voice rules are now applied retroactively across the EN public HTML surface. Section-level content not refreshed in this revision; the next pack release will catch Sections 02 through 06 up

to website v1.8.0 (brand assets in Section 03 design system, two new Indico scripts in Section 02 repo layout, the writing-voice rules in Section 06 admin guide) and address the table-of-contents page-numbers structural improvement deferred from this pass. Tracked at [#122](#).

v1.9.2 · May 2026 · Layout patch

Follow-up layout patch on v1.9.1. Three issues survived the first pass. **Figures 9 and 10** (ESSC live programme, Network directory) rendered the full 1280 × 3200 source screenshot at print width, so each figure spanned more than one PDF page, stranding its `h2` on the page before and leaving the next page nearly empty. Fixed with a `.snapshot.cropped` variant: an inner `.clip` div caps the image at 170 mm with `overflow:hidden`, the caption sits inside the wrapper but outside the overflow context, and both figures now sit on one page directly below their heading. Captions explicitly note the crop and point readers at the live URL for the full surface.

Heading + following block: `h2`, `h3`, `h4` all gain `break-after: avoid-page` + `page-break-after: avoid` so a sub-heading no longer strands when its first block is tall. **Section 05 SEO first page:** the chapter banner + intro paragraph rendered alone on page 34 because the `table` rule still carried `break-inside: avoid-page` from earlier styling, bonding the `h2` "What's in place" to its 10-row table and pushing the pair to page 35. Switching the table to `break-inside: auto` (with `tr { break-inside: avoid-page }` so individual rows still stay intact) lets the table start in whatever space remains on the chapter's first page and continue onto the next. No content edits.

v1.9.1 · May 2026 · Layout patch

Layout-only patch on the v1.9.0 content. **Page numbers** now render bottom-right via a `@bottom-right { content: counter(page) }` margin box on the default `@page` rule, suppressed on the cover, the promotional poster, and the A3 image plate. **Section-banner break:** `.section-banner` gains `break-after: avoid-page` so the chapter banner stays with the first content block rather than getting orphaned when the next block is large enough to push itself to a fresh page. **Two-up grid:** `.grid-2` gains `break-inside: avoid-page` so the Feature inventory's two cards stay together. **Site screenshots:** `build.sh --shots` bumped the Chrome viewport from 1280×1600 to 1280×3200 and the virtual-time budget from 5 s to 12 s, so the IntersectionObserver-gated reveal-on-scroll sections on the home page have actually rendered by the time the screenshot fires; `snap-home.png` went from 0.78 MB (empty canvas above the hero) to 2.4 MB (full content visible). No content edits to Sections 01–07 or to any appendix prose. No new feature shipped, per the minor-vs-patch rule ([README.md](#) → Versioning).

v1.9.0 · May 2026 · Section-level catch-up to website v1.7.0

The pack's substantive content was last refreshed at website v1.3.0. Five releases have shipped since: Pagefind search and the Phase 1 IA pass (v1.4.0), the launch-QA polish and hybrid release-notes format (v1.5.0), the live ESSC programme with member-aware speaker popovers (v1.6.0), the pre-conference polish wave (v1.6.1), and the directory keyword pipeline with the release-time automation that now keeps the pack in sync (v1.7.0). This revision catches Sections 02 through 06 up to that state, refreshes the screenshots, and trims the typography of this appendix so it ages better.

Front-facing additions documented

Section 02 site graph and page inventory now record fifteen public pages instead of the previous ten: `about.html`, `news.html`, `roadmap.html`, `outputs.html` (all v1.4.0) and `essc-2026.html` (v1.6.0). The feature inventory grows with site-wide Pagefind search built at deploy time, the live ESSC programme with parallel-session cards plus livestream and room badges plus member-aware speaker popovers, the directory research-interest keyword pipeline (sentence-case normalisation through `data/keyword-aliases.json`, canonical chips on bio cards, filter chip row above the grid with URL-hash persistence so filtered views are shareable), and the `/calendar.ics` webcal feed.

Backend pipeline documented

Two new data-flow diagrams join Section 02: the Indico-to-live-programme pipeline (daily sync, `indico.json` write, `events.json` patching via `indicoEventId`, `calendar.ics` regeneration, PR on `indico-sync/auto`) and the roadmap autostamp (any PR touching `CHANGELOG.md` fires `sync-roadmap.yml`, which rewrites the AUTOSTAMP block in `docs/roadmap-2026.md`). The repo-layout listing absorbs the new scripts: `sync-indico.py`, `sync-roadmap.py`, `promote-roadmap.py`, the matching `test-sync-*.py` + `test-promote-roadmap.py` files, `check-css-class-collisions.py`, the new `data/` entries (`events.json`, `indico.json`, `keyword-aliases.json`, `i18n-state.json`), and the new workflow files.

Dev process documented

Section 06 Admin guide picks up three current realities. The release pipeline now does work humans used to: `scripts/release.sh` calls `scripts/promote-roadmap.py` before the release commit, which flips the matching planned card to shipped across EN + FR + DE with locale-correct date formats, inserts the localised release-notes link, and bumps the *Last updated* stamp. On minor / major releases the same script prints a structured PDF cover-bump reminder, and on every release lists the issues still tagged with the milestone you're about to cut. The three sync workflows are now uniformly PR-based with auto-merge armed in the workflow itself: `sync-bios.yml`, `sync-indico.yml`, `sync-roadmap.yml`. The Google Forms photo-replacement workaround is documented in `docs/bios-setup.md` Step 1 as a known upstream limitation (#183).

Appendix typography overhaul

This appendix used to give every entry a multi-bullet treatment, which scales poorly: the doc was on its twelfth revision before this catch-up. From now on the current revision keeps the lede + themed sub-sections + index format, and earlier entries collapse to a one-paragraph summary. Per-entry body type is dropped from the document's reading size to 9.5 pt with tighter line-height. The intent is the same as the hybrid format on the website CHANGELOG: prose where it earns its keep, terser as it ages.

Index of changes

Added

- Five new pages on the site graph (Figure 4): `about.html`, `news.html`, `roadmap.html`, `outputs.html`, `essc-2026.html`. Page inventory rows for each.
- Two new data-flow sequence diagrams in Section 02: Indico-to-live-programme and roadmap autostamp.
- Feature inventory entries for Pagefind search, ESSC live programme, directory research-interest keyword pipeline, `calendar.ics` webcal feed.
- New repository-layout entries: `sync-indico.py`, `sync-roadmap.py`, `promote-roadmap.py`, test files, data files, new workflows.
- New v1.9.0 changelog entry (this one) with lede + themes + index format.
- Two new site screenshots: `snap-essc-2026.png` (live programme grid) and `snap-about.png` (consolidated About page).

Changed

- Section 02 site-structure intro updated from "ten public pages" to "fifteen".
- Section 02 page-inventory annotations: `people.html` now reads `data/keyword-aliases.json` in addition to `bios.json`.
- Section 04 translation posture: paragraph on `window.netsect` as the runtime-label helper used by the newer components.
- Section 05 SEO: note on the autostamp workflow's relationship with `sitemap.xml` (the autostamp writes to `roadmap-2026.md`, not the sitemap).
- Section 06 Admin guide: Reviewing a weekly sync PR now covers three workflows.

- Section 06 Admin guide: Cutting a release walks through the new release.sh behaviour (promote-roadmap, PDF reminder, open-issue audit).
- Three existing screenshots refreshed against the current site: [snap-home.png](#) , [snap-network.png](#) , [snap-grants.png](#) .
- Cover, poster footer, last-page footer, HTML `<title>` all stamped **v1.9.0**.
- Changelog appendix typography: 9.5 pt body, tighter line-height, current revision keeps hybrid format, older revisions compressed.

v1.8.0 • May 2026

Cover bump only. Records the gap to website v1.6.0 (live ESSC programme on netsec-cost.eu sourced from a daily Indico sync; member-aware speaker links with a glass preview popover; collapsible Shipped list on the public roadmap; CSS class-collision lint; persistent deep-link spotlight on the directory). Section-level content still reflected website v1.3.0; the catch-up was tracked in [issue #122](#) and shipped in this revision (v1.9.0).

v1.7.0 • May 2026

Cover bump only. Records the gap to website v1.4.0 (site-wide Pagefind search; Phase 1 IA pass adding About / news / outputs / roadmap pages; iCalendar feed; brand favicon) and v1.5.0 (launch-QA pass; accessibility statement v1.2; hybrid release-notes format adopted across the whole CHANGELOG). Section-level content not refreshed in this revision.

v1.6.0 • May 2026

Section-level catch-up to website v1.2.0 to v1.3.0. Site graph in Section 02 rewritten to ten public pages, with the *Find out more* discovery grid and *For NetSec members* strip surfaced explicitly. Page inventory extended with [licensing.html](#) , [press-kit.html](#) , [faq.html](#) , [glossary.html](#) . Repository layout reflects current scripts and data files. Screenshots refreshed.

v1.5.2 • May 2026

Appendix shuffle: promotional poster moves to Appendix C, changelog to Appendix D (so the pack ends on its changelog rather than the poster image). Full-bleed poster page introduced via a dedicated `@page promo-plate { margin: 0 }` rule, eliminating the blank pages that flanked the previous A3 raster. Global doc footer moves with the appendix shuffle so the version stamp still sits on the very last page.

v1.5.1 • May 2026

HTML `<title>` now carries the documentation-pack version, so the file's PDF metadata and the browser tab surface it without opening the cover. Author affiliation simplified on the cover and last-page footer from *ETH Zurich CSS* to *ETH Zurich*.

v1.5.0 • May 2026

New Appendix D Promotional poster: an outward-facing A3 portrait of the Action embedded as the final two pages of the pack. Source HTML at [docs/promo/poster-promo.html](#) ; rendered raster at [docs/pdf/poster-promo.png](#) (2480 × 3508 px). Use cases: conference print runs, departmental noticeboards, members' Wiki press kit, email outreach, COST annual reporting. Global doc footer relocated to the new appendix's text page. (*Re-ordered in v1.5.2.*)

v1.4.1 • May 2026

Clarification on PAT permissions for the automation account. The previous handover checklist called for `Administration: read+write` as the steady state; that overstated what the script needs. The ruleset bypass against `protect-main` is keyed to the user's repo *Admin* role, not to the PAT's `Administration` permission. Steady-state automation can run with `Administration: Read` (or none at all); re-grant `read+write` temporarily only when a ruleset adjustment is needed.

v1.4.0 • May 2026

New Section 07 subsection: Branch and tag protection. Documents the two GitHub rulesets now enforcing on the repo (`protect-main` , `protect-release-tags`) and why the tag ruleset has no bypass for anyone. Admin guide handover checklist rewritten around the consequence that the release-cutter needs the repo *Admin* role, with four sub-checklists (access grants, automation handover, verification, revocation).

v1.3.0 • May 2026

Semantic Versioning adopted for this pack from v1.0.0 onwards, matching the wider release convention (see `README.md` Versioning and the root `CHANGELOG.md`). Earlier covers' v1.0 / v1.1 / v1.2 are re-stamped as v1.0.0 / v1.1.0 / v1.2.0 in the entries below; content unchanged. Admin guide gains a *Cutting a release* subsection walking through `scripts/release.sh` . Repository tagged `v1.0.0` on 20 May 2026, marking Deliverable D1 ready for review.

v1.2.0 • May 2026 (was: v1.2)

New Section 07 Security & DevSecOps: threat model, coordinated-disclosure policy, GitHub-native automation inventory (private vulnerability reporting, security advisories, Dependabot alerts, CodeQL on push / pull-request / weekly cron, secret scanning with push protection), supply-chain hardening (pinned Actions, least-privilege `GITHUB_TOKEN`), web-platform hardening (HTTPS-only, HSTS, no third-party trackers), account hygiene, personal-data minimisation. Appendix B split: security promoted to Section 07; Appendix B now licensing only. New Appendix C Changelog (this appendix).

v1.1.0 • May 2026 (was: v1.1)

New full-bleed poster page after the cover with the website in numbers (30 countries, 49 MC members, 4 Working Groups, 5 grant schemes) and eight headline features. New Section 04 Translation posture: sibling-file approach for FR/DE beta, drift-checker workflow, explicit no-machine-translation stance. New Section 05 SEO & discoverability: Open Graph, Twitter Card, JSON-LD, canonical URLs, hreflang, sitemap, 404 strategy; `inject-seo.py` idempotent generator. DNS row clarified: Namecheap, registered under Dr Moritz Weiss with Dr Arthur Laudrain as admin contact.

v1.0.0 • May 2026 (was: v1.0)

Initial release of the documentation pack as part of Deliverable D1. Cover, table of contents, six core chapters (Overview & purpose, Architecture with data-flow diagrams for the weekly sync workflows, Design system, Admin guide, Appendix A Accessibility, Appendix B Security & Licensing as a single combined appendix in this revision). Three site screenshots, Mermaid diagrams inlined and rendered client-side at build time. Build pipeline (`docs/pdf/build.sh`) using a local HTTP server plus Chrome headless `--print-to-pdf` , no external services.

NetSec: Networking European Security Knowledge · COST Action CA24154 · MoU 063/25 · Running 10 Oct 2025 to 09 Oct 2029.

Documentation v1.9.4 · Compiled June 2026 by Dr Arthur Laudrain (MC member, CH; ETH Zurich) as part of Deliverable D1.

The views expressed are those of the Action and do not necessarily reflect those of COST or the European Union.